

UNITED NATIONS ECONOMIC COMMISSION FOR EUROPE  
Inland Transport Committee

---

# ATP

---

as amended on 30 September 2015

Agreement on the International Carriage  
of Perishable Foodstuffs and on the Special  
Equipment to be Used for such Carriage



UNITED NATIONS

ECONOMIC COMMISSION FOR EUROPE  
Inland Transport Committee

---

# ATP

---

**as amended on 30 September 2015**

**Agreement on the International Carriage  
of Perishable Foodstuffs and on the Special  
Equipment to be Used for such Carriage**



**UNITED NATIONS  
New York and Geneva, 2015**

## NOTE

The designations employed and the presentation of the material in this publication do not imply the expression of any opinion whatsoever on the part of the Secretariat of the United Nations concerning the legal status of any country, territory, city or area, or of its authorities, or concerning the delimitation of its frontiers or boundaries.

|               |
|---------------|
| ECE/TRANS/249 |
|---------------|

Copyright © United Nations, 2015

*All rights reserved.*

*No part of this publication may, for sales purposes, be reproduced, stored in a retrieval system or transmitted in any form or by any means, electronic, electrostatic, magnetic tape, mechanical, photocopying or otherwise, without prior permission in writing from the United Nations.*

|                               |
|-------------------------------|
| UNITED NATIONS PUBLICATION    |
| <i>Sales No.: E.15.VIII.2</i> |
| ISBN 978-92-1-139153-4        |
| eISBN 978-92-1-057257-6       |

## **United Nations Economic Commission for Europe (UNECE)**

The United Nations Economic Commission for Europe (UNECE) is one of the five United Nations regional commissions, administered by the Economic and Social Council (ECOSOC). It was established in 1947 with the mandate to help rebuild post-war Europe, develop economic activity and strengthen economic relations among European countries, and between Europe and the rest of the world. During the Cold War, UNECE served as a unique forum for economic dialogue and cooperation between East and West. Despite the complexity of this period, significant achievements were made, with consensus reached on numerous harmonization and standardization agreements.

In the post-Cold War era, UNECE acquired not only many new member States, but also new functions. Since the early 1990s the organization has focused on analyses of the transition process, using its harmonization experience to facilitate the integration of central and eastern European countries into global markets.

UNECE is the forum where the countries of western, central and eastern Europe, Central Asia and North America – 56 countries in all – come together to forge the tools of their cooperation. That cooperation concerns economic cooperation and integration, statistics, environment, transport, trade, sustainable energy, forestry and timber, housing and land management and population. The Commission offers a regional framework for the elaboration and harmonization of conventions, norms and standards. The Commission's experts provide technical assistance to the countries of South-East Europe and the Commonwealth of Independent States. This assistance takes the form of advisory services, training seminars and workshops where countries can share their experiences and best practices.

## **Transport in UNECE**

The UNECE Transport Division is the secretariat of the Inland Transport Committee (ITC) and the ECOSOC Committee of Experts on the Transport of Dangerous Goods and on the Globally Harmonized System of Classification and Labelling of Chemicals. The ITC and its 17 working parties, as well as the ECOSOC Committee and its sub-committees are intergovernmental decision-making bodies that work to improve the daily lives of people and businesses around the world in measurable ways and with concrete actions that enhance traffic safety, environmental performance, energy efficiency and the competitiveness of the transport sector.

The ECOSOC Committee was set up in 1953 by the Secretary-General at the request of the Economic and Social Council to elaborate recommendations on the transport of dangerous goods. Its mandate was extended to the global (multisectoral) harmonization of systems of classification and labelling of chemicals in 1999. It is composed of experts from countries which possess the relevant expertise and experience in the international trade and transport of dangerous goods and chemicals. Its membership is restricted in order to reflect a proper geographical balance between all regions of the world and to ensure adequate participation of developing countries. Although the Committee is a subsidiary body of ECOSOC, the Secretary-General decided in 1963 that the secretariat services would be provided by the UNECE Transport Division.

The Inland Transport Committee is a unique intergovernmental forum that was set up in 1947 to support the reconstruction of transport connections in post-war Europe. Over the years it has specialized in facilitating the harmonized and sustainable development of inland modes of transport. The main results of this persevering and ongoing work are reflected among other things (i) in 58 United Nations conventions and many more technical regulations which are updated on a regular basis and provide an international legal framework for the sustainable development of national and international road, rail, inland water and intermodal transport, as well as the transport of dangerous goods and the construction and inspection of road motor vehicles; (ii) in the Trans-European Motorways, Trans-European Railways and the Euro-Asia Transport Links projects that facilitate multi-country coordination of transport infrastructure investment programmes; (iii) in the TIR system which is a global customs transit facilitation solution; (iv) in the tool called For Future Inland Transport Systems (ForFITS) which can assist national and local governments to monitor CO<sub>2</sub> emissions coming from inland transport modes and to select and design climate change mitigation policies based on their impact and adapted to local conditions; (v) in transport statistics – methods and data – that are internationally agreed on; and (vi) in studies and reports that help transport policy development by addressing timely issues based on cutting-edge research and analysis.

ITC also devotes special attention to Intelligent Transport Services, sustainable urban mobility and city logistics, as well as to increasing the resilience of transport networks and services in response to climate change adaptation and security challenges.

## FOREWORD

The Agreement on the International Carriage of Perishable Foodstuffs and on the Special Equipment to be Used for such Carriage (ATP) done at Geneva on 1 September 1970 entered into force on 21 November 1976.

The Agreement and its annexes have been regularly amended and updated since their entry into force by the Working Party on the Transport of Perishable Foodstuffs (WP.11) of the Economic Commission for Europe's Inland Transport Committee.

### **Territorial applicability**

The ATP is an Agreement between States, and there is no overall enforcing authority. In practice, highway checks are carried out by Contracting Parties, and non-compliance may then result in legal action by national authorities against offenders in accordance with their domestic legislation. ATP itself does not prescribe any penalties. At the time of publishing, those Contracting Parties are Albania, Andorra, Austria, Azerbaijan, Belarus, Belgium, Bosnia and Herzegovina, Bulgaria, Croatia, Czech Republic, Denmark, Estonia, Finland, France, Georgia, Germany, Greece, Hungary, Ireland, Italy, Kazakhstan, Kyrgyzstan, Latvia, Lithuania, Luxembourg, Monaco, Montenegro, Morocco, Netherlands, Norway, Poland, Portugal, Republic of Moldova, Romania, Russian Federation, Saudi Arabia, Serbia, Slovakia, Slovenia, Spain, Sweden, Tajikistan, The former Yugoslav Republic of Macedonia, Tunisia, Turkey, Ukraine, United Kingdom of Great Britain and Northern Ireland, United States of America and Uzbekistan.

### **Additional practical information**

Any query concerning the application of ATP should be directed to the relevant competent authority. Additional information may also be found on the UNECE Transport Division web site at the following link:

<http://www.unece.org/trans/main/wp11/atp.html>

This information, updated on a continuous basis, concerns:

- The status of ATP;
- Depository notifications (e.g. new Contracting Parties, amendments or corrections to legal texts);
- Publication details (corrections, publication of new amendments);
- List and details of competent authorities and ATP Test Stations.

The text below comprises the Agreement itself and its annexes with the latest amendments which enter into force on 30 September 2015.

The amendments or corrections to the Agreement which have become applicable since the last edition of this publication are in Annex 1, paragraph 4; Annex 1, Appendix 1, paragraphs 3 and 6; Annex 1, Appendix 2, paragraphs 4.3.2, 6.3, 7 and 8; Annex 1, Appendix 3A and Appendix 3B; Annex 1, Appendix 4; and Annex 2, Appendix 1.

## TABLE OF CONTENTS

|  | <b>Page</b> |
|--|-------------|
| <b>AGREEMENT ON THE INTERNATIONAL CARRIAGE OF PERISHABLE FOODSTUFFS AND ON THE SPECIAL EQUIPMENT TO BE USED FOR SUCH CARRIAGE (ATP).....</b>   | <b>1</b>    |
| <b><u>Annex 1</u></b>  |             |
| DEFINITIONS OF AND STANDARDS FOR SPECIAL EQUIPMENT FOR THE CARRIAGE OF PERISHABLE FOODSTUFFS .....   | 9           |
| 1. Insulated equipment.....  | 9           |
| 2. Refrigerated equipment.....   | 9           |
| 3. Mechanically refrigerated equipment .....   | 10          |
| 4. Heated equipment .....  | 10          |
| <b>Annex 1, Appendix 1</b>   |             |
| Provisions relating to the checking of insulated, refrigerated, mechanically refrigerated or heated equipment for compliance with the standards.....   | 11          |
| <b>Annex 1, Appendix 2</b>   |             |
| Methods and procedures for measuring and checking the insulating capacity and the efficiency of the cooling or heating appliances of special equipment for the carriage of perishable foodstuffs ..... | 15          |
| 1. Definitions and general principles .....  | 15          |
| 2. Insulating capacity of equipment .....  | 16          |
| 3. Effectiveness of thermal appliances of equipment.....   | 19          |
| 4. Procedure for measuring the effective refrigerating capacity $W_o$ of a unit when the evaporator is free from frost.....  | 22          |
| 5. Checking the insulating capacity of equipment in service.....   | 25          |
| 6. Verifying the effectiveness of thermal appliances of equipment in service .....   | 27          |
| 7. Procedure for measuring the capacity of mechanical multi-temperature refrigeration units and dimensioning multi-compartment equipment.....  | 29          |
| 8. Test reports .....  | 33          |

**Table of contents (cont'd)**

|   | <b>Page</b> |
|---|-------------|
| <b><i>Models of Test Reports</i></b>  |             |
| MODEL No. 1 A .....   | 34          |
| MODEL No. 1 B.....  | 36          |
| MODEL No. 2 A.....  | 38          |
| MODEL No. 2 B.....  | 40          |
| MODEL No. 3 .....   | 42          |
| MODEL No. 4 A.....  | 43          |
| MODEL No. 4 B.....  | 45          |
| MODEL No. 4 C.....  | 48          |
| MODEL No. 5 .....   | 50          |
| MODEL No. 6 .....   | 53          |
| MODEL No. 7 .....   | 54          |
| MODEL No. 8 .....   | 56          |
| MODEL No. 9 .....   | 58          |
| MODEL No. 10 .....  | 60          |
| <b>Annex 1, Appendix 3</b> .....  | <b>65</b>   |
| A. Model form of certificate of compliance of the equipment,<br>as prescribed in Annex 1, Appendix 1, paragraph 3 ..... | 65          |
| B. Certification plate of compliance of the equipment,<br>as provided for in Annex 1, Appendix 1, paragraph 3 .....     | 68          |
| <b>Annex 1, Appendix 4</b>  |             |
| Distinguishing marks to be affixed to special equipment .....   | 71          |



**Table of contents (cont'd)**

|  | <b>Page</b> |
|--|-------------|
| <b><u>Annex 2</u></b>  |             |
| SELECTION OF EQUIPMENT AND TEMPERATURE<br>CONDITIONS TO BE OBSERVED FOR THE CARRIAGE<br>OF QUICK (DEEP)-FROZEN AND FROZEN FOODSTUFFS ..... | 73          |
| <b>Annex 2, Appendix 1</b>   |             |
| Monitoring of air temperatures for transport of perishable foodstuffs quick-frozen .....   | 75          |
| <b>Annex 2, Appendix 2</b>   |             |
| Procedure for the sampling and measurement of temperature for carriage of chilled,<br>frozen and quick-frozen perishable foodstuffs .....  | 77          |
| <b><u>Annex 3</u></b>  |             |
| SELECTION OF EQUIPMENT AND TEMPERATURE<br>CONDITIONS TO BE OBSERVED FOR THE CARRIAGE<br>OF CHILLED FOODSTUFFS.....                         | 81          |

**AGREEMENT ON THE INTERNATIONAL CARRIAGE OF PERISHABLE FOODSTUFFS  
AND ON THE SPECIAL EQUIPMENT TO BE USED FOR SUCH CARRIAGE (ATP)**

THE CONTRACTING PARTIES,

DESIROUS of improving the conditions of preservation of the quality of perishable foodstuffs during their carriage, particularly in international trade,

CONSIDERING that the improvement of those conditions is likely to promote the expansion of trade in perishable foodstuffs,

HAVE AGREED as follows:

**Chapter I**

**SPECIAL TRANSPORT EQUIPMENT**

**Article 1**

For the international carriage of perishable foodstuffs, equipment shall not be designated as "insulated", "refrigerated", "mechanically refrigerated", or "heated" equipment unless it complies with the definitions and standards set forth in annex 1 to this Agreement.

**Article 2**

The Contracting Parties shall take the measures necessary to ensure that the equipment referred to in article 1 of this Agreement is inspected and tested for compliance with the said standards in conformity with the provisions of annex 1, appendices 1, 2, 3 and 4, to this Agreement. Each Contracting Party shall recognize the validity of certificates of compliance issued in conformity with annex 1, appendix 1, paragraph 3 to this Agreement by the competent authority of another Contracting Party. Each Contracting Party may recognize the validity of certificates of compliance issued in conformity with the requirements of annex 1, appendices 1 and 2, to this Agreement by the competent authority of a State not a Contracting Party.

**Chapter II**

**USE OF SPECIAL TRANSPORT EQUIPMENT FOR THE INTERNATIONAL  
CARRIAGE OF CERTAIN PERISHABLE FOODSTUFFS**

**Article 3**

1. The provisions of article 4 of this Agreement shall apply to all carriage, whether for hire or reward or for own account, carried out exclusively - subject to the provisions of paragraph 2 of this article - by rail, by road or by a combination of the two, of

- quick (deep)-frozen and frozen foodstuffs, and of
- foodstuffs referred to in annex 3 to this Agreement even if they are neither quick (deep)-frozen nor frozen,

if the point at which the goods are, or the equipment containing them is, loaded on to a rail or road vehicle and the point at which the goods are, or the equipment containing them is, unloaded from that vehicle are in two different States and the point at which the goods are unloaded is situated in the territory of a Contracting Party.

In the case of carriage entailing one or more sea crossings other than sea crossings as referred to in paragraph 2 of this article, each land journey shall be considered separately.

2. The provisions of paragraph 1 of this article shall likewise apply to sea crossings of less than 150 km on condition that the goods are shipped in equipment used for the land journey or journeys without transloading of the goods and that such crossings precede or follow one or more land journeys as referred to in paragraph 1 of this article or take place between two such land journeys.

3. Notwithstanding the provisions of paragraphs 1 and 2 of this article, the Contracting Parties need not apply the provisions of article 4 of this Agreement to the carriage of foodstuffs not intended for human consumption.

#### **Article 4**

1. For the carriage of the perishable foodstuffs specified in annexes 2 and 3 to this Agreement, the equipment referred to in article 1 of this Agreement shall be used unless the temperatures to be anticipated throughout carriage render this requirement manifestly unnecessary for the purpose of maintaining the temperature conditions specified in annexes 2 and 3 to this Agreement. The equipment shall be so selected and used that the temperature conditions prescribed in the said annexes can be complied with throughout carriage. Furthermore, all appropriate measures shall be taken, more particularly as regards the temperature of the foodstuffs at the time of loading and as regards icing or re-icing during the journey or other necessary operations. Nevertheless, the provisions of this paragraph shall apply only in so far as they are not incompatible with international undertakings in the matter of international carriage arising for the Contracting Parties by virtue of conventions in force at the time of the entry into force of this Agreement or by virtue of conventions substituted for them.

2. If during carriage under this Agreement the provisions of paragraph 1 of this article have not been complied with,

- (a) the foodstuffs may not be disposed of in the territory of a Contracting Party after completion of carriage unless the competent authorities of that Contracting Party deem it compatible with the requirements of public health to authorize such disposal and unless such conditions as the authorities may attach to the authorization when granting it are fulfilled; and
- (b) every Contracting Party may, by reason of the requirements of public health or zooprophyllaxis and in so far as it is not incompatible with the other international undertakings referred to in the last sentence of paragraph 1 of this article, prohibit the entry of the foodstuffs into its territory or make their entry subject to such conditions as it may determine.

3. Compliance with the provisions of paragraph 1 of this article shall be required of carriers for hire or reward only in so far as they have undertaken to procure or provide services intended to ensure such compliance and if such compliance depends on the performance of those services. If other persons, whether individuals or corporate bodies, have undertaken to procure or provide services intended to ensure compliance with the provisions of this Agreement, they shall be required to ensure such compliance in so far as it depends on performance of the services they have undertaken to procure or provide.

4. During carriage which is subject to the provisions of this Agreement and for which the loading point is situated in the territory of a Contracting Party, responsibility for compliance with the requirements of paragraph 1 of this article shall rest, subject to the provisions of paragraph 3 of this article,

- in the case of transport for hire or reward, with the person, whether an individual or a corporate body, who is the consignor according to the transport document or, in the absence of a transport document, with the person, whether an individual or a corporate body, who has entered into the contract of carriage with the carrier;
- in other cases with the person, whether an individual or a corporate body, who performs carriage.

### **Chapter III**

#### **MISCELLANEOUS PROVISIONS**

##### **Article 5**

The provisions of this Agreement shall not apply to carriage in containers classified as thermal maritime by land without transloading of the goods where such carriage is preceded or followed by a sea crossing other than a sea crossing as referred to in article 3, paragraph 2, of this Agreement.

##### **Article 6**

1. Each Contracting Party shall take all appropriate measures to ensure observance of the provisions of this Agreement. The competent administrations of the Contracting Parties shall keep one another informed of the general measures taken for this purpose.

2. If a Contracting Party discovers a breach committed by a person residing in the territory of another Contracting Party, or imposes a penalty upon such a person, the administration of the first Party shall inform the administration of the other Party of the breach discovered and of the penalty imposed.

##### **Article 7**

The Contracting Parties reserve the right to enter into bilateral or multilateral agreements to the effect that provisions applicable to special equipment and provisions applicable to the temperatures at which certain foodstuffs are required to be maintained during carriage may, more particularly by reason of special climatic conditions, be more stringent than those prescribed in this Agreement. Such provisions shall apply only to international carriage between Contracting Parties which have concluded bilateral or multilateral agreements as referred to in this article. Such agreements shall be transmitted to the Secretary-General of the United Nations, who shall communicate them to Contracting Parties to this Agreement which are not signatories of the said agreements.

##### **Article 8**

Failure to observe the provisions of this Agreement shall not affect either the existence or the validity of contracts entered into for the performance of carriage.

### **Chapter IV**

#### **FINAL PROVISIONS**

##### **Article 9**

1. States members of the Economic Commission for Europe and States admitted to the Commission in a consultative capacity under paragraph 8 of the Commission's terms of reference may become Contracting Parties to this Agreement

- (a) by signing it;
- (b) by ratifying it after signing it subject to ratification; or
- (c) by acceding to it.

2. States which may participate in certain activities of the Economic Commission for Europe under paragraph 11 of the Commission's terms of reference may become Contracting Parties to this Agreement by acceding thereto after its entry into force.

3. This Agreement shall be open for signature until 31 May 1971 inclusive. Thereafter, it shall be open for accession.
4. Ratification or accession shall be effected by the deposit of an instrument with the Secretary-General of the United Nations.

#### **Article 10**

1. Any State may at the time of signing this Agreement without reservation as to ratification or of depositing its instrument of ratification or accession or at any time thereafter declare by notification addressed to the Secretary-General of the United Nations that the Agreement does not apply to carriage performed in any or in a particular one of its territories situated outside Europe. If notification as aforesaid is made after the entry into force of the Agreement in respect of the notifying State the Agreement shall, ninety days after the date on which the Secretary-General has received the notification, cease to apply to carriage in the territory or territories named in that notification. New Contracting Parties acceding to ATP as from 30 April 1999 and applying paragraph 1 of this article shall not be entitled to enter any objection to draft amendments in accordance with the procedure provided for in article 18, paragraph 2.
2. Any State which has made a declaration under paragraph 1 of this article may at any time thereafter declare by notification addressed to the Secretary-General of the United Nations that the Agreement will be applicable to carriage performed in a territory named in the notification made under paragraph 1 of this article and the Agreement shall become applicable to carriage in that territory one hundred and eighty days after the date on which the Secretary-General has received that notification.

#### **Article 11**

1. This Agreement shall come into force one year after five of the States referred to in its article 9, paragraph 1, have signed it without reservation as to ratification or have deposited their instruments of ratification or accession.
2. With respect to any State which ratifies, or accedes to, this Agreement after five States have signed it without reservation as to ratification or have deposited their instruments of ratification or accession, this Agreement shall enter into force one year after the said State has deposited its instrument of ratification or accession.

#### **Article 12**

1. Any Contracting Party may denounce this Agreement by giving notice of denunciation to the Secretary-General of the United Nations.
2. The denunciation shall take effect fifteen months after the date on which the Secretary-General received the notice of denunciation.

#### **Article 13**

This Agreement shall cease to have effect if the number of Contracting Parties is less than five throughout any period of twelve consecutive months after its entry into force.

#### **Article 14**

1. Any State may at the time of signing this Agreement without reservation as to ratification or of depositing its instrument of ratification or accession or at any time thereafter declare by notification addressed to the Secretary-General of the United Nations that this Agreement will be applicable to all or any of the territories for the international relations of which that State is responsible. This Agreement shall be applicable to the territory or territories named in the notification as from the ninetieth day after receipt of the notice by the Secretary-General or, if on that day the Agreement has not yet entered into force, as from its entry into force.

2. Any State which has made a declaration under paragraph 1 of this article making this Agreement applicable to a territory for whose international relations it is responsible may denounce the Agreement separately in respect of that territory in conformity with article 12 hereof.

#### **Article 15**

1. Any dispute between two or more Contracting Parties concerning the interpretation or application of this Agreement shall so far as possible be settled by negotiation between them.

2. Any dispute which is not settled by negotiation shall be submitted to arbitration if any one of the Contracting Parties concerned in the dispute so requests and shall be referred accordingly to one or more arbitrators selected by agreement between those Parties. If within three months from the date of the request for arbitration, the Parties concerned in the dispute are unable to agree on the selection of an arbitrator or arbitrators, any of those Parties may request the Secretary-General of the United Nations to designate a single arbitrator to whom the dispute shall be referred for decision.

3. The decision of the arbitrator or arbitrators designated under the preceding paragraph shall be binding on the Contracting Parties concerned in the dispute.

#### **Article 16**

1. Any State may, at the time of signing, ratifying, or acceding to, this Agreement, declare that it does not consider itself bound by article 15, paragraphs 2 and 3 of this Agreement. The other Contracting Parties shall not be bound by these paragraphs with respect to any Contracting Party which has entered such a reservation.

2. Any Contracting Party which has entered a reservation under paragraph 1 of this article may at any time withdraw the reservation by notification addressed to the Secretary-General of the United Nations.

3. With the exception of the reservation provided for in paragraph 1 of this article, no reservation to this Agreement shall be permitted.

#### **Article 17**

1. After this Agreement has been in force for three years, any Contracting Party may, by notification addressed to the Secretary-General of the United Nations, request that a conference be convened for the purpose of revising this Agreement. The Secretary-General shall notify all Contracting Parties of the request and a revision conference shall be convened by the Secretary-General if, within a period of four months from the date of the notification sent by the Secretary-General, not less than one third of the Contracting Parties signify their assent to the request.

2. If a conference is convened in pursuance of paragraph 1 of this article, the Secretary-General shall so advise all the Contracting Parties and invite them to submit within a period of three months, the proposals which they wish the conference to consider. The Secretary-General shall circulate the provisional agenda for the conference, together with the text of such proposals, to all Contracting Parties not less than three months before the date on which the conference is to open.

3. The Secretary-General shall invite to any conference convened in pursuance of this article all the countries referred to in article 9, paragraph 1, of this Agreement, and also the countries which have become Contracting Parties under the said article 9, paragraph 2.

## Article 18

1. Any Contracting Party may propose one or more amendments to this Agreement. The text of any proposed amendment shall be communicated to the Secretary-General of the United Nations, who shall communicate it to all Contracting Parties and bring it to the notice of all the other States referred to in article 9, paragraph 1, of this Agreement.

The Secretary-General may also propose amendments to this Agreement or to its annexes which have been transmitted to him by the Working Party on the Transport of Perishable Foodstuffs of the Inland Transport Committee of the Economic Commission for Europe.

2. Within a period of six months following the date on which the proposed amendment is communicated by the Secretary-General, any Contracting Party may inform the Secretary-General

- (a) that it has an objection to the amendment proposed, or
- (b) that, although it intends to accept the proposal, the conditions necessary for such acceptance are not yet fulfilled in its country.

3. If a Contracting Party sends the Secretary-General a communication as provided for in paragraph 2 (b) of this article, it may, so long as it has not notified the Secretary-General of its acceptance, submit an objection to the proposed amendment within a period of nine months following the expiry of the period of six months prescribed in respect of the initial communication.

4. If an objection to the proposed amendment is stated in accordance with the terms of paragraphs 2 and 3 of this article, the amendment shall be deemed not to have been accepted and shall be of no effect.

5. If no objection to the proposed amendment has been stated in accordance with paragraphs 2 and 3 of this article, the amendment shall be deemed to have been accepted on the date specified below:

- (a) if no Contracting Party has sent a communication to the Secretary-General in accordance with paragraph 2 (b) of this article, on the expiry of the period of six months referred to in paragraph 2 of this article;
- (b) if at least one Contracting Party has sent a communication to the Secretary-General in accordance with paragraph 2 (b) of this article, on the earlier of the following two dates:
  - the date by which all the Contracting Parties which sent such communications have notified the Secretary-General of their acceptance of the proposed amendment, subject however to the proviso that if all the acceptances were notified before the expiry of the period of six months referred to in paragraph 2 of this article the date shall be the date of expiry of that period;
  - the date of expiry of the period of nine months referred to in paragraph 3 of this article.

6. Any amendment deemed to be accepted shall enter into force six months after the date on which it was deemed to be accepted.

7. The Secretary-General shall as soon as possible inform all Contracting Parties whether an objection to the proposed amendment has been stated in accordance with paragraph 2 (a) of this article and whether one or more Contracting Parties have sent him a communication in accordance with paragraph 2 (b) of this article. If one or more Contracting Parties have sent him such a communication, he shall subsequently inform all the Contracting Parties whether the Contracting Party or Parties which have sent such a communication raise an objection to the proposed amendment or accept it.



8. Independently of the amendment procedure laid down in paragraphs 1 to 6 of this article, the annexes and appendices to this Agreement may be modified by agreement between the competent administrations of all the Contracting Parties. If the administration of a Contracting Party has stated that under its national law its agreement is contingent on special authorization or on the approval of a legislative body, the consent of the Contracting Party concerned to the modification of an annex shall not be deemed to have been given until the Contracting Party has notified the Secretary-General that the necessary authorization or approval has been obtained. The agreement between the competent administrations may provide that, during a transitional period, the old annexes shall remain in force, wholly or in part, concurrently with the new annexes. The Secretary-General shall specify the date of the entry into force of the new texts resulting from such modifications.

### **Article 19**

In addition to communicating to them the notifications provided for in articles 17 and 18 of this Agreement, the Secretary-General of the United Nations shall notify the States referred to in article 9, paragraph 1, of this Agreement and the States which have become Contracting Parties under article 9, paragraph 2, of:

- (a) signatures, ratifications and accessions under article 9;
- (b) the dates of entry into force of this Agreement pursuant to article 11;
- (c) denunciations under article 12;
- (d) the termination of this Agreement under article 13;
- (e) notifications received under articles 10 and 14;
- (f) declarations and notifications received under article 16, paragraphs 1 and 2;
- (g) the entry into force of any amendment pursuant to article 18.

### **Article 20**

After 31 May 1971, the original of this Agreement shall be deposited with the Secretary-General of the United Nations, who shall transmit certified true copies to each of the States mentioned in article 9, paragraphs 1 and 2, of this Agreement.

**IN WITNESS WHEREOF**, the undersigned, being duly authorized thereto, have signed this Agreement.

**DONE** at Geneva, this first day of September, one thousand nine hundred and seventy, in a single copy, in the English, French and Russian languages, the three texts being equally authentic.





## Annex I

### **DEFINITIONS OF AND STANDARDS FOR SPECIAL EQUIPMENT <sup>1</sup> FOR THE CARRIAGE OF PERISHABLE FOODSTUFFS**

1. **Insulated equipment.** Equipment of which the body <sup>2</sup> is built with insulating walls, doors, floor and roof, by which heat exchanges between the inside and outside of the body can be so limited that the overall coefficient of heat transfer (K coefficient) is such that the equipment is assignable to one or other of the following two categories:

$I_N$  = Normally insulated equipment specified by: - a K coefficient equal to or less than  $0.70 \text{ W/m}^2 \cdot \text{K}$ ;

$I_R$  = Heavily insulated equipment specified by: - a K coefficient equal to or less than  $0.40 \text{ W/m}^2 \cdot \text{K}$  and by side-walls with a thickness of at least 45 mm for transport equipment of a width greater than 2.50 m.

The definition of the K coefficient and a description of the method to be used in measuring it are given in appendix 2 to this annex.

2. **Refrigerated equipment.** Insulated equipment which, using a source of cold (natural ice, with or without the addition of salt; eutectic plates; dry ice, with or without sublimation control; liquefied gases, with or without evaporation control, etc.) other than a mechanical or "absorption" unit, is capable, with a mean outside temperature of  $+ 30 \text{ }^\circ\text{C}$ , of lowering the temperature inside the empty body to, and thereafter maintaining it:

At  $+ 7 \text{ }^\circ\text{C}$  maximum in the case of class A;

At  $- 10 \text{ }^\circ\text{C}$  maximum in the case of class B;

At  $- 20 \text{ }^\circ\text{C}$  maximum in the case of class C; and

At  $0 \text{ }^\circ\text{C}$  maximum in the case of class D.

If such equipment includes one or more compartments, receptacles or tanks for the refrigerant, the said compartments, receptacles or tanks shall:

be capable of being filled or refilled from the outside; and

have a capacity in conformity with the provisions of annex 1, appendix 2, paragraph 3.1.3.

The K coefficient of refrigerated equipment of classes B and C shall in every case be equal to or less than  $0.40 \text{ W/m}^2 \cdot \text{K}$ .

---

<sup>1</sup> Wagons, lorries, trailers, semi-trailers, containers and other similar equipment.

<sup>2</sup> In the case of tank equipment, the term "body" means under this definition, the tank itself.

3. **Mechanically refrigerated equipment.** Insulated equipment either fitted with its own refrigerating appliance, or served jointly with other units of transport equipment by such an appliance (fitted with either a mechanical compressor, or an "absorption" device, etc.). The appliance shall be capable, with a mean outside temperature of + 30 °C, of lowering the temperature  $T_i$  inside the empty body to, and thereafter maintaining it continuously in the following manner at:

In the case of classes A, B and C, any desired practically constant inside temperature  $T_i$  in conformity with the standards defined below for the three classes:

Class A. Mechanically refrigerated equipment fitted with a refrigerating appliance such that  $T_i$  may be chosen between + 12 °C and 0 °C inclusive;

Class B. Mechanically refrigerated equipment fitted with a refrigerating appliance such that  $T_i$  may be chosen between + 12 °C and - 10 °C inclusive;

Class C. Mechanically refrigerated equipment fitted with a refrigerating appliance such that  $T_i$  may be chosen between + 12 °C and - 20 °C inclusive.

In the case of classes D, E and F a fixed practically constant inside temperature  $T_i$  in conformity with the standards defined below for the three classes:

Class D. Mechanically refrigerated equipment fitted with a refrigerating appliance such that  $T_i$  is equal to or less than 0 °C;

Class E. Mechanically refrigerated equipment fitted with a refrigerating appliance such that  $T_i$  is equal to or less than - 10 °C;

Class F. Mechanically refrigerated equipment fitted with a refrigerating appliance such that  $T_i$  is equal to or less than - 20 °C. The K coefficient of equipment of classes B, C, E and F shall in every case be equal to or less than 0.40 W/m<sup>2</sup>.K.

4. **Heated equipment.** Insulated equipment, which is capable of raising the inside temperature of the empty body to, and thereafter maintaining it for not less than 12 hours without renewal of supply at, a practically constant value of not less than + 12 °C when the mean outside temperature, is as indicated below:

-10 °C in the case of class A heated equipment;

-20 °C in the case of class B heated equipment;

-30° C in the case of class C heated equipment;

-40° C in the case of class D heated equipment.

Heat producing appliances shall have a capacity in conformity with the provisions of annex 1, appendix 2, paragraphs 3.3.1 to 3.3.5.

The K coefficient of equipment of classes B, C and D shall in every case be equal to or less than 0.40 W/m<sup>2</sup>.K.

## **Annex 1, Appendix 1**

### **PROVISIONS RELATING TO THE CHECKING OF INSULATED, REFRIGERATED, MECHANICALLY REFRIGERATED OR HEATED EQUIPMENT FOR COMPLIANCE WITH THE STANDARDS**

1. Checks for conformity with the standards prescribed in this annex shall be made:
  - (a) before equipment enters into service;
  - (b) periodically, at least once every six years;
  - (c) whenever required by the competent authority.

Except in the cases provided for in appendix 2, sections 5 and 6, to this annex, the checks shall be made at a testing station designated or approved by the competent authority of the country in which the equipment is registered or recorded, unless, in the case of the check referred to in (a) above, a check has already been made on the equipment itself or on its prototype in a testing station designated or approved by the competent authority of the country in which the equipment was manufactured.

2. The methods and procedures to be used in checking for compliance with the standards are described in appendix 2 to this annex.
3. A certificate of compliance with the standards shall be issued by the competent authority of the country in which the equipment is to be registered or recorded. This certificate shall conform to the model reproduced in appendix 3 to this annex.

The certificate of compliance shall be carried on the equipment during carriage and be produced whenever so required by the control authorities. However, if a certification plate of compliance, as reproduced in appendix 3 to this annex, is fixed to the equipment, the certification plate of compliance shall be recognized as equivalent to a certificate of compliance. A certification plate of compliance may be fixed to the equipment only when a valid certificate of compliance is available. Certification plates of compliance shall be removed as soon as the equipment ceases to conform to the standards laid down in this annex.

In the case of equipment transferred to another country, which is a Contracting Party to ATP, it shall be accompanied by the following documents so that the competent authority of the country in which the equipment is to be registered or recorded can issue a certificate of compliance:

- (a) in all cases, the test report of the equipment itself or, in the case of serially produced equipment, of the reference equipment;
- (b) in all cases, the certificate of compliance issued by the competent authority of the country of manufacture or, for equipment in service, the competent authority of the country of registration. This certificate will be treated as a provisional certificate if necessary with a maximum validity of six months;
- (c) in the case of serially produced equipment, the technical specification of the equipment to be certified as issued by the manufacturer of the equipment or his duly accredited representative (this specification shall cover the same items as the descriptive pages concerning the equipment which appear in the test report and shall be drawn up in at least one of the official languages).

In the case of equipment transferred after it has been in use, the equipment may be subject to a visual inspection to confirm its identity before the competent authority of the country, in which it is to be registered or recorded, issues a certificate of compliance.

For a batch of identical serially produced insulated equipment (containers) having an internal volume of less than 2 m<sup>3</sup>, a certificate of compliance for the batch may be issued by the competent authority. In such cases the identification numbers of all the insulated equipment, or the first and the last identification numbers of the series, shall be indicated on the certificate of compliance instead of the serial number of each individual unit. In that case, the insulated equipment listed in that certificate shall be fitted with a certification plate of compliance as described in Annex 1, Appendix 3 B issued by the competent authority.

In the case of transfer of this insulated equipment (containers) to another country which is a Contracting Party to this Agreement in order to be registered or recorded there, the competent authority of the country of the new registration or recording may provide an individual certificate of compliance based on the original certificate of compliance established for the whole batch.

4. Distinguishing marks and particulars shall be affixed to the equipment in conformity with the provisions of appendix 4 to this annex. They shall be removed as soon as the equipment ceases to conform to the standards laid down in this annex.
5. The insulated bodies of "insulated", "refrigerated", "mechanically refrigerated" or "heated" transport equipment and their thermal appliances shall each bear a durable manufacturer's plate firmly affixed by the manufacturer in a conspicuous and readily accessible position on a part not subject to replacement in use. It shall be able to be checked easily and without the use of tools. For insulated bodies, the manufacturer's plate shall be on the outside of the body. The manufacturer's plate shall show clearly and indelibly at least the following particulars:<sup>3</sup>

Country of manufacture or letters used in international road traffic;

Name of manufacturer or company;

Model (figures and/or letters);

Serial number;

Month and year of manufacture.

6. (a) New equipment of a specific type serially produced may be approved by testing one unit of that type. If the unit tested meets the class specification, the resulting test report shall be regarded as a Type Approval Certificate. This certificate shall expire at the end of a period of six years beginning from the date of completion of the test.

The date of expiry of test reports shall be stated in months and years.

- (b) The competent authority shall take steps to verify that production of other units is in conformity with the approved type. For this purpose it may check by testing sample units drawn at random from the production series.

- (c) A unit shall not be regarded as being of the same type as the unit tested unless it satisfies the following minimum conditions:

- (i) If it is insulated equipment, in which case the reference equipment may be insulated, refrigerated, mechanically refrigerated or heated equipment,

the construction shall be comparable and, in particular, the insulating material and the method of insulation shall be identical;

---

<sup>3</sup> *These requirements shall apply to new plates only. A transitional period of three months shall be granted from the date of entry into force of this requirement.*

the thickness of the insulating material shall be not less than that of the reference equipment;

the interior fittings shall be identical or simplified;

the number of doors and the number of hatches or other openings shall be the same or less; and

the inside surface area of the body shall not be as much as 20% greater or smaller;

minor and limited modifications of added or exchanged interior and exterior fittings may be permitted:<sup>4</sup>

if the equivalent volume of accumulated insulation material of all such modifications is less than 1/100th of the total volume of the insulating material in the insulated unit;

if the K coefficient of the tested reference equipment, corrected by a calculation of the added thermal losses, is less than or equal to the K coefficient limit of the category of the equipment; and

if such modifications of interior fittings are carried out using the same technique, particularly as concerns glued fittings.

All modifications shall be done by or be approved by the manufacturer of the insulated equipment.

(ii) If it is refrigerated equipment, in which case the reference equipment shall be refrigerated equipment,

the conditions set out under (i) above shall be satisfied;

inside circulating fans shall be comparable;

the source of cold shall be identical; and

the reserve of cold per unit of inside surface area shall be greater or equal;

(iii) If it is mechanically refrigerated equipment, in which case the reference equipment shall be either:

(a) mechanically refrigerated equipment;

- the conditions set out in (i) above shall be satisfied; and

- the effective refrigerating capacity of the mechanical refrigeration appliance per unit of inside surface area, under the same temperature conditions, shall be greater or equal; or

(b) insulated equipment which is complete in every detail but minus its mechanical refrigeration unit which will be fitted at a later date.

---

<sup>4</sup> *The present provisions regarding minor and limited modifications apply to equipment manufactured after the date of their entry into force (30 September 2015).*

The resulting aperture will be filled, during the measurement of the K coefficient, with close fitting panels of the same overall thickness and type of insulation as is fitted to the front wall. In which case:

- the conditions set out in (i) above shall be satisfied; and
- the effective refrigerating capacity of the mechanical refrigeration unit fitted to insulated reference equipment shall be as defined in annex 1, appendix 2, paragraph 3.2.6.

(iv) If it is heated equipment, in which case the reference equipment may be insulated or heated equipment,

- the conditions set out under (i) above shall be satisfied;
- the source of heat shall be identical; and
- the capacity of the heating appliance per unit of inside surface area shall be greater or equal.

(d) If, in the course of the six-year period, the production series exceeds 100 units, the competent authority shall determine the percentage of units to be tested.

## Annex I, Appendix 2

### **METHODS AND PROCEDURES FOR MEASURING AND CHECKING THE INSULATING CAPACITY AND THE EFFICIENCY OF THE COOLING OR HEATING APPLIANCES OF SPECIAL EQUIPMENT FOR THE CARRIAGE OF PERISHABLE FOODSTUFFS**

#### **1. DEFINITIONS AND GENERAL PRINCIPLES**

- 1.1 K coefficient. The overall heat transfer coefficient (K coefficient) of the special equipment is defined by the following formula:

$$K = \frac{W}{S \cdot \Delta T}$$

where W is either the heating power or the cooling capacity, as the case may be, required to maintain a constant absolute temperature difference  $\Delta T$  between the mean inside temperature  $T_i$  and the mean outside temperature  $T_e$ , during continuous operation, when the mean outside temperature  $T_e$  is constant for a body of mean surface area S.

- 1.2 The mean surface area S of the body is the geometric mean of the inside surface area  $S_i$  and the outside surface area  $S_e$  of the body:

$$S = \sqrt{S_i \cdot S_e}$$

In determining the two surface areas  $S_i$  and  $S_e$ , structural peculiarities and surface irregularities of the body, such as chamfers, wheel-arches and similar features, shall be taken into account and shall be noted under the appropriate heading in test reports; however, if the body is covered with corrugated sheet metal the area considered shall be that of the plane surface occupied, not that of the developed corrugated surface.

#### **Temperature measuring points**

- 1.3 In the case of parallelepipedic bodies, the mean inside temperature of the body ( $T_i$ ) is the arithmetic mean of the temperatures measured 10 cm from the walls at the following 12 points:

- (a) The eight inside corners of the body; and
- (b) The centres of the four inside faces having the largest area.

If the body is not parallelepipedic, the 12 points of measurements shall be distributed as satisfactorily as possible having regard to the shape of the body.

- 1.4 In the case of parallelepipedic bodies, the mean outside temperature of the body ( $T_e$ ) is the arithmetic mean of the temperatures measured 10 cm from the walls at the following 12 points:

- (a) The eight outside corners of the body; and
- (b) The centres of the four outside faces having the largest area.

If the body is not parallelepipedic, the 12 points of measurement shall be distributed as satisfactorily as possible having regard to the shape of the body.



- 1.5 The mean temperature of the walls of the body is the arithmetic mean of the mean outside temperature of the body and the mean inside temperature of the body:

$$\frac{T_e + T_i}{2}$$

- 1.6 Temperature measuring instruments protected against radiation shall be placed inside and outside the body at the points specified in paragraphs 1.3 and 1.4 of this appendix.

#### **Steady state period and duration of test**

- 1.7 The mean outside temperatures and the mean inside temperatures of the body, taken over a steady period of not less than 12 hours, shall not vary by more than  $\pm 0.3$  K, and these temperatures shall not vary by more than  $\pm 1.0$  K during the preceding 6 hours.

The difference between the heating power or cooling capacity measured over two periods of not less than 3 hours at the start and at the end of the steady state period, and separated by at least 6 hours, shall be less than 3 %.

The mean values of the temperatures and heating or cooling capacity over at least the last 6 hours of the steady state period will be used in K coefficient calculation.

The mean inside and outside temperatures at the beginning and the end of the calculation period of at least 6 hours shall not differ by more than 0.2 K.

## **2. INSULATING CAPACITY OF EQUIPMENT**

### **Procedures for measuring the K coefficient**

#### **2.1 Equipment other than liquid-foodstuffs tanks**

- 2.1.1 The K coefficient shall be measured in continuous operation either by the internal cooling method or by the internal heating method. In either case, the empty body shall be placed in an insulated chamber.

#### **Test method**

- 2.1.2 Where the internal cooling method is used, one or more heat exchangers shall be placed inside the body. The surface area of these exchangers shall be such that, if a fluid at a temperature not lower than  $0\text{ }^{\circ}\text{C}$ <sup>5</sup> passes through them, the mean inside temperature of the body remains below  $+10\text{ }^{\circ}\text{C}$  when continuous operation has been established. Where the internal heating method is used, electrical heating appliances (resistors, etc.) shall be used. The heat exchangers or electrical heating appliances shall be fitted with fans having a delivery rate sufficient to obtain 40 to 70 air charges per hour related to the empty volume of the tested body, and the air distribution around all inside surfaces of the tested body shall be sufficient to ensure that the maximum difference between the temperatures of any 2 of the 12 points specified in paragraph 1.3 of this appendix does not exceed 2 K when continuous operation has been established.
- 2.1.3 Heat quantity: The heat dissipated by the electrical resistance fan heaters shall not exceed a flow of  $1\text{W}/\text{cm}^2$  and the heater units shall be protected by a casing of low emissivity.

The electrical energy consumption shall be determined with an accuracy of  $\pm 0.5\%$ .

---

<sup>5</sup> To prevent frosting.

## **Test procedure**

- 2.1.4 Whatever the method employed, the mean temperature of the insulated chamber shall throughout the test be kept uniform, and constant in compliance with paragraph 1.7 of this appendix, to within  $\pm 0.5$  K, at a level such that the temperature difference between the inside of the body and the insulated chamber is  $25\text{ }^{\circ}\text{C} \pm 2$  K, the average temperature of the walls of the body being maintained at  $+ 20\text{ }^{\circ}\text{C} \pm 0.5$  K.
- 2.1.5 During the test, whether by the internal cooling method or by the internal heating method, the mass of air in the chamber shall be made to circulate continuously so that the speed of movement of the air 10 cm from the walls is maintained at between 1 and 2 metres/second.
- 2.1.6 The appliances for generating and distributing cold or heat and for measuring the quantity of cold or heat exchanged and the heat equivalent of the air-circulating fans shall be started up. Electrical cable losses between the heat input measuring instrument and the tested body shall be established by a measurement or calculation and subtracted from the total heat input measured.
- 2.1.7 When continuous operation has been established, the maximum difference between the temperatures at the warmest and at the coldest points on the outside of the body shall not exceed 2 K.
- 2.1.8 The mean outside temperature and the mean inside temperature of the body shall each be read not less than four times per hour.

## **2.2 Liquid-foodstuffs tanks**

- 2.2.1 The method described below applies only to single-compartment or multiple-compartment tank equipment intended solely for the carriage of liquid foodstuffs such as milk. Each compartment of such tanks shall have at least one manhole and one discharge-pipe connecting socket; where there are several compartments they shall be separated from one another by non-insulated vertical partitions.
- 2.2.2 K coefficients shall be measured in continuous operation by internal heating of the empty tank in an insulated chamber.

### **Test method**

- 2.2.3 An electrical heating appliance (resistors, etc.) shall be placed inside the tank. If the tank has several compartments, an electrical heating appliance shall be placed in each compartment. The electrical heating appliances shall be fitted with fans with a delivery rate sufficient to ensure that the difference between the maximum temperature and the minimum temperature inside each compartment does not exceed 3 K when continuous operation has been established. If the tank comprises several compartments, the difference between the mean temperature in the coldest compartment and the mean temperature in the warmest compartment shall not exceed 2 K, the temperatures being measured as specified in paragraph 2.2.4 of this appendix.
- 2.2.4 Temperature measuring instruments protected against radiation shall be placed inside and outside the tank 10 cm from the walls, as follows:
- (a) If the tank has only one compartment, measurements shall be made at a minimum of 12 points positioned as follows:

The four extremities of two diameters at right angles to one another, one horizontal and the other vertical, near each of the two ends of the tank;

The four extremities of two diameters at right angles to one another, inclined at an angle of  $45^{\circ}$  to the horizontal, in the axial plane of the tank;

- (b) If the tank has two compartments, the measurements shall be made at least at the following points:

Near the end of the first compartment and near the partition with the second compartment, at the extremities of three radiuses forming  $120^\circ$  angles, one of the radiuses being directed vertically upwards.

Near the end of the second compartment and near the partition with the first compartment, at the extremities of three radiuses forming  $120^\circ$  angles, one of the radiuses being directed vertically downwards.

- (c) If the tank has several compartments, the points of measurement shall be as follows:

for each of the two end compartments, at least the following:

The extremities of a horizontal diameter near the end and the extremities of a vertical diameter near the partition;

and for each of the other compartments, at least the following:

The extremities of a diameter inclined at an angle of  $45^\circ$  to the horizontal near one of the partitions and the extremities of a diameter perpendicular to the first and near the other partition.

- (d) The mean inside temperature and the mean outside temperature of the tank shall respectively be the arithmetic mean of all the measurements taken inside and all the measurements taken outside the tank. In the case of tanks having at least two compartments, the mean inside temperature of each compartment shall be the arithmetic mean of the measurements made in the compartment, and the number of those measurements in each compartment shall be no less than four and the total number of measurements in all compartments of the tank shall be no less than twelve.

### **Test procedure**

- 2.2.5 Throughout the test, the mean temperature of the insulated chamber shall be kept uniform, and constant in compliance with paragraph 1.7 of this appendix, at a level such that the difference in temperature between the inside of the tank and that of the insulated chamber is not less than  $25^\circ\text{C} \pm 2\text{K}$ , with the average temperature of the tank walls being maintained at  $+20^\circ\text{C} \pm 0.5\text{K}$ .
- 2.2.6 The mass of air in the chamber shall be made to circulate continuously so that the speed of movement of the air 10 cm from the walls is maintained at between 1 and 2 metres/second.
- 2.2.7 The appliances for heating and circulating the air and for measuring the quantity of heat exchanged and the heat equivalent of the air-circulating fans shall be started up.
- 2.2.8 When continuous operation has been established, the maximum difference between the temperatures at the warmest and at the coldest points on the outside of the tank shall not exceed 2 K.
- 2.2.9 The mean outside temperature and the mean inside temperature of the tank shall each be read not less than four times per hour.

## 2.3 Provisions common to all types of insulated equipment

### 2.3.1 Verification of the K coefficient

Where the purpose of the tests is not to determine the K coefficient but simply to verify that it is below a certain limit, the tests carried out as described in paragraphs 2.1.1 to 2.2.9 of this appendix may be stopped as soon as the measurements made show that the K coefficient meets the requirements.

### 2.3.2 Accuracy of measurements of the K coefficient

Testing stations shall be provided with the equipment and instruments necessary to ensure that the K coefficient is determined with a maximum margin of error of  $\pm 10\%$  when using the method of internal cooling and  $\pm 5\%$  when using the method of internal heating.

## 3. EFFECTIVENESS OF THERMAL APPLIANCES OF EQUIPMENT

### Procedures for determining the efficiency of thermal appliances of equipment

#### 3.1 Refrigerated equipment

3.1.1 The empty equipment shall be placed in an insulated chamber whose mean temperature shall be kept uniform, and constant to within  $\pm 0.5$  K, at  $+30$  °C. The mass of air in the chamber shall be made to circulate as described in paragraph 2.1.5 of this appendix.

3.1.2 Temperature measuring instruments protected against radiation shall be placed inside and outside the body at the points specified in paragraphs 1.3 and 1.4 of this appendix.

#### Test procedure

- 3.1.3 (a) In the case of **equipment other than equipment with fixed eutectic plates, and equipment fitted with liquefied gas systems**, the maximum weight of refrigerant specified by the manufacturer or which can normally be accommodated shall be loaded into the spaces provided when the mean inside temperature of the body has reached the mean outside temperature of the body ( $+30$  °C). Doors, hatches and other openings shall be closed and the inside ventilation appliances (if any) of the equipment shall be started up at maximum capacity. In addition, in the case of new equipment, a heating appliance with a heating capacity equal to 35% of the heat exchanged through the walls in continuous operation shall be started up inside the body when the temperature prescribed for the class to which the equipment is presumed to belong has been reached. No additional refrigerant shall be loaded during the test;
- (b) In the case of **equipment with fixed eutectic plates**, the test shall comprise a preliminary phase of freezing of the eutectic solution. For this purpose, when the mean inside temperature of the body and the temperature of the plates have reached the mean outside temperature ( $+30$  °C), the plate-cooling appliance shall be put into operation for 18 consecutive hours after closure of the doors and hatches. If the plate-cooling appliance includes a cyclically-operating mechanism, the total duration of operation of the appliance shall be 24 hours. In the case of new equipment, as soon as the cooling appliance is stopped, a heating appliance with a heating capacity equal to 35% of the heat exchanged through the walls in continuous operation shall be started up inside the body when the temperature prescribed for the class to which the equipment is presumed to belong has been reached. The solution shall not be subjected to any re-freezing operation during the test;
- (c) In the case of **equipment fitted with liquefied gas systems**, the following test procedure shall be used: when the mean inside temperature of the body has reached the mean outside temperature ( $+30$  °C), the receptacles for the liquefied gas shall be filled to the

level prescribed by the manufacturer. Then the doors, hatches and other openings shall be closed as in normal operation and the inside ventilation appliances (if any) of the equipment shall be started up at maximum capacity. The thermostat shall be set at a temperature not more than 2 degrees below the limit temperature of the presumed class of the equipment. Cooling of the body then shall be commenced. During the cooling of the body the refrigerant consumed is simultaneously replaced. This replacement shall be effected:

either for a time corresponding to the interval between the commencement of cooling and the moment when the temperature prescribed for the class to which the equipment is presumed to belong is reached for the first time; or

for a duration of three hours counting from the commencement of cooling, whichever is shorter.

Beyond this period, no additional refrigerant shall be loaded during the test.

In the case of new equipment, a heating appliance with a heating capacity equal to 35% of the heat exchanged through the walls in continuous operation shall be started up inside the body when the class temperature has been reached.

### **Provisions common to all types of refrigerated equipment**

- 3.1.4 The mean outside temperature and the mean inside temperature of the body shall each be read not less often than once every 30 minutes.
- 3.1.5 The test shall be continued for 12 hours after the mean inside temperature of the body has reached the lower limit prescribed for the class to which the equipment is presumed to belong (A = +7 °C; B = -10 °C; C = -20 °C; D = 0 °C) or, in the case of equipment with fixed eutectic plates, after stoppage of the cooling appliance.

### **Criterion of satisfaction**

- 3.1.6 The test shall be deemed satisfactory if the mean inside temperature of the body does not exceed the aforesaid lower limit during the aforesaid period of 12 hours.

## **3.2 Mechanically refrigerated equipment**

### **Test method**

- 3.2.1 The test shall be carried out in the conditions described in paragraphs 3.1.1 and 3.1.2 of this appendix.

### **Test procedure**

- 3.2.2 When the mean inside temperature of the body reaches the outside temperature (+ 30 °C), the doors, hatches and other openings shall be closed and the refrigerating appliance and the inside ventilating appliances (if any) shall be started up at maximum capacity. In addition, in the case of new equipment, a heating appliance with a heating capacity equal to 35% of the heat exchanged through the walls in continuous operation shall be started up inside the body when the temperature prescribed for the class to which the equipment is presumed to belong has been reached.
- 3.2.3 The mean outside temperature and the mean inside temperature of the body shall each be read not less often than once every 30 minutes.

3.2.4 The test shall be continued for 12 hours after the mean inside temperature of the body has reached:

either the lower limit prescribed for the class to which the equipment is presumed to belong in the case of classes A, B and C (A = 0 °C; B = -10 °C; C = -20 °C); or

a level not lower than the upper limit prescribed for the class to which the equipment is presumed to belong in the case of classes D, E, and F (D = 0 °C; E = -10 °C; F = -20 °C).

#### **Criterion of satisfaction**

3.2.5 The test shall be deemed satisfactory if the refrigerating appliance is able to maintain the prescribed temperature conditions during the said 12-hour periods, with any automatic defrosting of the refrigerating unit not being taken into account.

3.2.6 If the refrigerating appliance with all its accessories has undergone separately, to the satisfaction of the competent authority, a test to determine its effective refrigerating capacity at the prescribed reference temperatures, the transport equipment may be accepted as mechanically refrigerated equipment without undergoing an efficiency test if the effective refrigerating capacity of the appliance in continuous operation exceeds the heat loss through the walls for the class under consideration, multiplied by the factor 1.75.

3.2.7 If the mechanically refrigerating unit is replaced by a unit of a different type, the competent authority may:

- (a) require the equipment to undergo the determinations and verifications prescribed in paragraphs 3.2.1 to 3.2.4; or
- (b) satisfy itself that the effective refrigerating capacity of the new mechanically refrigerating unit is, at the temperature prescribed for equipment of the class concerned, at least equal to that of the unit replaced; or
- (c) satisfy itself that the effective refrigerating capacity of the new mechanically refrigerating unit meets the requirements of paragraph 3.2.6.

### **3.3 Heated equipment**

#### **Test method**

3.3.1 The empty equipment shall be placed in an insulated chamber whose temperature shall be kept uniform and constant at as low a level as possible. The atmosphere of the chamber shall be made to circulate as described in paragraph 2.1.5 of this appendix.

3.3.2 Temperature measuring instruments protected against radiation shall be placed inside and outside the body at the points specified in paragraphs 1.3 and 1.4 of this appendix.

#### **Test procedure**

3.3.3 Doors, hatches and other openings shall be closed and the heating equipment and the inside ventilating appliances (if any) shall be started up at maximum capacity.

3.3.4 The mean outside temperature and the mean inside temperature of the body shall each be read not less often than once every 30 minutes.

3.3.5 The test shall be continued for 12 hours after the difference between the mean inside

temperature and the mean outside temperature of the body has reached the level corresponding to the conditions prescribed for the class to which the equipment is presumed to belong. In the case of new equipment, the above temperature difference shall be increased by 35 per cent.

#### **Criterion of satisfaction**

3.3.6 The test shall be deemed satisfactory if the heating appliance is able to maintain the prescribed temperature difference during the 12 hours aforesaid.

### **4. PROCEDURE FOR MEASURING THE EFFECTIVE REFRIGERATING CAPACITY $W_o$ OF A UNIT WHEN THE EVAPORATOR IS FREE FROM FROST**

#### **4.1 General principles**

4.1.1 When attached to either a calorimeter box or the insulated body of a unit of transport equipment, and operating continuously, this capacity is:

$$W_o = W_j + U \cdot \Delta T$$

where  $U$  is the heat leakage of the calorimeter box or insulated body, Watts/°C.

$\Delta T$  is the difference between the mean inside temperature  $T_i$  and the mean outside temperature  $T_e$  of the calorimeter or insulated body (K),

$W_j$  is the heat dissipated by the fan heater unit to maintain each temperature difference in equilibrium.

#### **4.2 Test method**

4.2.1 The refrigeration unit is either fitted to a calorimeter box or the insulated body of a unit of transport equipment.

In each case, the heat leakage is measured at a single mean wall temperature prior to the capacity test. An arithmetical correction factor, based upon the experience of the testing station, is made to take into account the average temperature of the walls at each thermal equilibrium during the determination of the effective refrigerating capacity.

It is preferable to use a calibrated calorimeter box to obtain maximum accuracy.

Measurements and procedure shall be as described in paragraphs 1.1 to 2.1.8 above; however, it is sufficient to measure  $U$  the heat leakage only, the value of this coefficient being defined by the following relationship:

$$U = \frac{W}{\Delta T_m}$$

where:

$W$  is the heating power (in Watts) dissipated by the internal heater and fans;

$\Delta T_m$  is the difference between the mean internal temperature  $T_i$  and the mean external temperature  $T_e$ ;

$U$  is the heat flow per degree of difference between the air temperature inside and outside the calorimeter box or unit of transport equipment measured with the refrigeration unit fitted.



The calorimeter box or unit of transport equipment is placed in a test chamber. If a calorimeter box is used,  $U \cdot \Delta T$  should be not more than 35% of the total heat flow  $W_o$ .

The calorimeter box or unit of transport equipment shall be heavily insulated.

#### 4.2.2 Instrumentation

Test stations shall be equipped with instruments to measure the U value to an accuracy of  $\pm 5\%$ . Heat transfer through air leakage should not exceed 5% of the total heat transfer through the calorimeter box or through the insulated body of the unit of transport equipment. The refrigerating capacity shall be determined with an accuracy of  $\pm 5\%$ .

The instrumentation of the calorimeter box or unit of transport equipment shall conform to paragraphs 1.3 and 1.4 above. The following are to be measured:

- (a) *Air temperatures:* At least four thermometers uniformly distributed at the inlet to the evaporator;

At least four thermometers uniformly distributed at the outlet to the evaporator;

At least four thermometers uniformly distributed at the air inlet(s) to the refrigeration unit;

The thermometers shall be protected against radiation.

The accuracy of the temperature measuring system shall be  $\pm 0.2$  K;

- (b) *Energy consumption:* Instruments shall be provided to measure the electrical energy or fuel consumption of the refrigeration unit.

The electrical energy and fuel consumption shall be determined with an accuracy of  $\pm 0.5\%$ ;

- (c) *Speed of rotation:* Instruments shall be provided to measure the speed of rotation of the compressors and circulating fans or to allow these speeds to be calculated where direct measurement is impractical.

The speed of rotation shall be measured to an accuracy of  $\pm 1\%$ ;

- (d) *Pressure:* High precision pressure gauges (accurate to  $\pm 1\%$ ) shall be fitted to the condenser and evaporator and to the compressor inlet when the evaporator is fitted with a pressure regulator.

#### 4.2.3 Test conditions

- (i) The average air temperature at the inlet(s) to the refrigeration unit shall be maintained at  $30\text{ }^\circ\text{C} \pm 0.5$  K.

The maximum difference between the temperatures at the warmest and at the coldest points shall not exceed 2 K.

- (ii) Inside the calorimeter box or the insulated body of the unit of transport equipment (at the air inlet to the evaporator): there shall be three levels of temperature between  $-25\text{ }^\circ\text{C}$  and  $+12\text{ }^\circ\text{C}$  depending on the characteristics of the unit, one temperature level being at the minimum prescribed for the class requested by the manufacturer with a tolerance of  $\pm 1$  K.



The mean inside temperature shall be maintained within a tolerance of  $\pm 0.5$  K. During the measurement of refrigerating capacity, the heat dissipated within the calorimeter box or the insulated body of the unit of transport equipment shall be maintained at a constant level with a tolerance of  $\pm 1\%$ .

When presenting a refrigeration unit for test, the manufacturer shall supply:

- Documents describing the unit to be tested;
- A technical document outlining the parameters that are most important to the functioning of the unit and specifying their allowable range;
- The characteristics of the equipment series tested; and
- A statement as to which prime mover(s) shall be used during testing.

### **4.3 Test procedure**

4.3.1 The test shall be divided into two major parts, the cooling phase and the measurement of the effective refrigerating capacity at three increasing temperature levels.

- (a) Cooling phase; the initial temperature of the calorimeter box or transport equipment shall be  $30\text{ °C} \pm 3\text{ K}$ . It shall then be lowered to the following temperatures:  $-25\text{ °C}$  for  $-20\text{ °C}$  class,  $-13\text{ °C}$  for  $-10\text{ °C}$  class or  $-2\text{ °C}$  for  $0\text{ °C}$  class;
- (b) Measurement of effective refrigerating capacity, at each internal temperature level.

A first test to be carried out, for at least four hours at each level of temperature, under control of the thermostat (of the refrigeration unit) to stabilize the heat transfer between the interior and exterior of the calorimeter box or unit of transport equipment.

A second test shall be carried out without the thermostat in operation in order to determine the maximum refrigerating capacity, with the heating power of the internal heater producing an equilibrium condition at each temperature level as prescribed in paragraph 4.2.3.

The duration of the second test shall be not less than four hours.

Before changing from one temperature level to another, the box or unit shall be manually defrosted.

If the refrigeration unit can be operated by more than one form of energy, the tests shall be repeated accordingly.

If the compressor is driven by the vehicle engine, the test shall be carried out at both the minimum speed and at the nominal speed of rotation of the compressor as specified by the manufacturer.

If the compressor is driven by the vehicle motion, the test shall be carried out at the nominal speed of rotation of the compressor as specified by the manufacturer.

4.3.2 The same procedure shall be followed for the enthalpy method described below, but in this case the heat power dissipated by the evaporator fans at each temperature level shall also be measured.

This method may, alternatively, be used to test reference equipment. In this case, the effective

refrigerating capacity is measured by multiplying the mass flow ( $m$ ) of the refrigerant liquid by the difference in enthalpy between the refrigerant vapour leaving the unit ( $h_o$ ) and the liquid at the inlet to the unit ( $h_i$ ).

To obtain the effective refrigerating capacity, the heat generated by the evaporator fans ( $W_f$ ) is deducted. It is difficult to measure  $W_f$  if the evaporator fans are driven by an external motor, in this particular case the enthalpy method is not recommended. When the fans are driven by internal electric motors, the electrical power is measured by appropriate instruments with an accuracy of  $\pm 3\%$ , with refrigerant flow measurement being accurate to  $\pm 3\%$ .

The heat balance is given by the formula:

$$W_o = (h_o - h_i) m - W_f.$$

Appropriate methods are described in standards ISO 917, BS 3122, DIN, NEN, etc. An electric heater is placed inside the equipment in order to obtain the thermal equilibrium.

#### 4.3.3 Precautions

As the tests for effective refrigerating capacity are carried out with the thermostat of the refrigeration unit disconnected, the following precautions shall be observed:

If the equipment has a hot gas injection system, it shall be inoperative during the test;

with automatic controls of the refrigeration unit which unload individual cylinders (to tune the capacity of the refrigeration unit to motor output) the test shall be carried out with the number of cylinders appropriate for the temperature.

#### 4.3.4 Checks

The following should be verified and the methods used indicated on the test report:

- (i) the defrosting system and the thermostat are functioning correctly;
- (ii) the rate of air circulation is that specified by the manufacturer.

If the air circulation of a refrigeration unit's evaporator fans is to be measured, methods capable of measuring the total delivery volume shall be used. Use of one of the relevant existing standards, i.e. BS 848, ISO 5801, AMCA 210-85, AMCA 210-07, DIN 24163, NFE 36101, NF X10.102, DIN 4796 is recommended;

- (iii) the refrigerant used for tests is that specified by the manufacturer.

### 4.4 **Test result**

- 4.4.1 The refrigeration capacity for ATP purposes is that relating to the mean temperature at the inlet(s) of the evaporator. The temperature measuring instruments shall be protected against radiation.

## 5. **CHECKING THE INSULATING CAPACITY OF EQUIPMENT IN SERVICE**

For the purpose of checking the insulating capacity of each piece of equipment in service as prescribed in appendix 1, paragraphs 1 (b) and 1 (c), to this annex, the competent authorities may:

Apply the methods described in paragraphs 2.1.1 to 2.3.2 of this appendix; or

Appoint experts to assess the fitness of the equipment for retention in one or other of the categories of insulated equipment. These experts shall take the following particulars into account and shall base their conclusions on information as indicated below.

### **5.1 General examination of the equipment**

This examination shall take the form of an inspection of the equipment to determine the following:

- (i) the durable manufacturer's plate affixed by the manufacturer;
- (ii) the general design of the insulating sheathing;
- (iii) the method of application of insulation;
- (iv) the nature and condition of the walls;
- (v) the condition of the insulated compartment;
- (vi) the thickness of the walls;

and to make all appropriate observations concerning the effective insulating capacity of the equipment. For this purpose the experts may cause parts of the equipment to be dismantled and require all documents they may need to consult (plans, test reports, specifications, invoices, etc.) to be placed at their disposal.

### **5.2 Examination for air-tightness (not applicable to tank equipment)**

The inspection shall be made by an observer stationed inside the equipment, which shall be placed in a brightly-illuminated area. Any method yielding more accurate results may be used.

### **5.3 Decisions**

- (i) If the conclusions regarding the general condition of the body are favourable, the equipment may be kept in service as insulated equipment of its initial class for a further period of not more than three years. If the conclusions of the expert or experts are not acceptable, the equipment may be kept in service only following a satisfactory measurement of the K coefficient according to the procedure described in paragraphs 2.1.1 to 2.3.2 of this appendix; it may then be kept in service for a further period of six years.
- (ii) In the case of heavily insulated equipment, if the conclusions of an expert or experts show the body to be unsuitable for keeping in service in its initial class but suitable for continuing in service as normally insulated equipment, then the body may be kept in service in an appropriate class for a further three years. In this case, the distinguishing marks (as in appendix 4 of this annex) shall be changed appropriately.
- (iii) If the equipment consists of units of serially-produced equipment of a particular type satisfying the requirements of appendix 1, paragraph 6, to this annex and belonging to one owner, then in addition to an inspection of each unit of equipment, the K coefficient of not less than 1% of the number of units involved, may be measured in conformity with the provisions of sections 2.1, 2.2 and 2.3 of this appendix. If the results of the examinations and measurements are acceptable, all the equipment in question may be kept in service as insulating equipment of its initial class for a further period of six years.

**6. VERIFYING THE EFFECTIVENESS OF THERMAL APPLIANCES OF EQUIPMENT IN SERVICE**

To verify as prescribed in appendix 1, paragraphs 1 (b) and 1 (c), to this annex the effectiveness of the thermal appliance of each item of refrigerated, mechanically refrigerated or heated equipment in service, the competent authorities may:

Apply the methods described in sections 3.1, 3.2 and 3.3 of this appendix; or

Appoint experts to apply the particulars described in sections 5.1 and 5.2 of this appendix when applicable as well as the following provisions:

**6.1 Refrigerated equipment other than equipment with fixed eutectic accumulators**

It shall be verified that the inside temperature of the empty equipment, previously brought to the outside temperature, can be brought to the limit temperature of the class to which the equipment belongs, as prescribed in this annex, and maintained below the said limit temperature for a period *t*

$$\text{such that } t \geq \frac{12\Delta T}{\Delta T'}$$

in which

$\Delta T$  is the difference between + 30 °C and the said limit temperature, and

$\Delta T'$  is the difference between the mean outside temperature during the test and the class limit temperature, the outside temperature being not lower than + 15 °C.

If the results are acceptable, the equipment may be kept in service as refrigerated equipment of its initial class for a further period of not more than three years.

**6.2 Mechanically refrigerated equipment**

(i) Equipment constructed from 2 January 2012

It shall be verified that, when the outside temperature is not lower than + 15 °C, the inside temperature of the empty equipment can be brought to the class temperature within a maximum period (in minutes), as prescribed in the table below:

| Outside temperature | 30  | 29  | 28  | 27  | 26  | 25  | 24  | 23  | 22  | 21  | 20  | 19  | 18  | 17  | 16  | 15  | °C  |
|---------------------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| Class C, F          | 360 | 350 | 340 | 330 | 320 | 310 | 300 | 290 | 280 | 270 | 260 | 250 | 240 | 230 | 220 | 210 | min |
| Class B, E          | 270 | 262 | 253 | 245 | 236 | 228 | 219 | 211 | 202 | 194 | 185 | 177 | 168 | 160 | 151 | 143 | min |
| Class A, D          | 180 | 173 | 166 | 159 | 152 | 145 | 138 | 131 | 124 | 117 | 110 | 103 | 96  | 89  | 82  | 75  | min |

The inside temperature of the empty equipment must have been previously brought to the outside temperature.

If the results are acceptable, the equipment may be kept in service as mechanically refrigerated equipment of its initial class for a further period of not more than three years.

(ii) Transitional provisions applicable to equipment in service

For equipment constructed prior to the date given in 6.2 (i), the following provisions shall apply:

It shall be verified that, when the outside temperature is not lower than +15° C, the inside temperature of the empty equipment, which has been previously brought to the outside

temperature, can be brought within a maximum period of six hours:

In the case of equipment in classes A, B or C, to the minimum temperature, as prescribed in this annex;

In the case of equipment in classes D, E or F, to the limit temperature, as prescribed in this annex.

If the results are acceptable, the equipment may be kept in service as mechanically refrigerated equipment of its initial class for a further period of not more than three years.

### **6.3 Heated equipment**

It shall be verified that the difference between the inside temperature of the equipment and the outside temperature which governs the class to which the equipment belongs as prescribed in this annex (a difference of 22 K in the case of class A, 32 K in the case of class B, 42 K in the case of class C and 52 K in the case of class D) can be achieved and be maintained for not less than 12 hours. If the results are acceptable, the equipment may be kept in service as heated equipment of its initial class for a further period of not more than three years.

### **6.4 Temperature measuring points**

Temperature measuring points protected against radiation shall be placed inside the body and outside the body.

For measuring the inside temperature of the body ( $T_i$ ), at least 2 temperature measuring points shall be placed inside the body at a maximum distance of 50 cm from the front wall, 50 cm from the rear door at a height of a minimum of 15 cm and a maximum of 20 cm above the floor area.

For measuring the outside temperature of the body ( $T_e$ ), at least 2 temperature measuring points shall be placed at a distance of at least 10 cm from an outer wall of the body and at least 20 cm from the air inlet of the condenser unit.

The final reading should be from the warmest point inside the body and the coldest point outside.

### **6.5 Provisions common to refrigerated, mechanically refrigerated and heated equipment**

- (i) If the results are not acceptable, refrigerated, mechanically refrigerated or heated equipment may be kept in service in its initial class only if it passes at a testing station the tests described in sections 3.1, 3.2 and 3.3 of this appendix; it may then be kept in service in its initial class for a further period of six years.
- (ii) If the equipment consists of units of serially-produced refrigerated, mechanically refrigerated or heated equipment of a particular type satisfying the requirements of appendix 1, paragraph 6, to this annex and belonging to one owner, then in addition to an inspection of the thermal appliances to ensure that their general condition appears to be satisfactory, the effectiveness of the cooling or heating appliances of not less than 1% of the number of units may be determined at a testing station in conformity with the provisions of sections 3.1, 3.2 and 3.3 of this appendix. If the results of the examinations and of the determination of effectiveness are acceptable, all the equipment in question may be kept in service in its initial class for a further period of six years.

## **7. PROCEDURE FOR MEASURING THE CAPACITY OF MECHANICAL MULTI-TEMPERATURE REFRIGERATION UNITS AND DIMENSIONING MULTI-COMPARTMENT EQUIPMENT**

### **7.1 Definitions**

- (a) Multi-compartment equipment: Equipment with two or more insulated compartments for maintaining a different temperature in each compartment;
- (b) Multi-temperature mechanical refrigeration unit: Mechanical refrigeration unit with compressor and common suction inlet, condenser and two or more evaporators set at different temperatures in the various compartments of multi-compartment equipment;
- (c) Host unit: Refrigeration unit with or without an integral evaporator;
- (d) Unconditioned compartment: a compartment considered to have no evaporator or for which the evaporator is inactive for the purposes of dimensioning calculations and certification;
- (e) Multi-temperature operation: Operation of a multi-temperature mechanical refrigeration unit with two or more evaporators operating at different temperatures in multi-compartment equipment;
- (f) Nominal refrigerating capacity: Maximum refrigerating capacity of the refrigeration unit in mono-temperature operation with two or three evaporators operating simultaneously at the same temperature;
- (g) Individual refrigerating capacity ( $P_{\text{ind-evap}}$ ): The maximum refrigerating capacity of each evaporator in solo operation with the host unit;
- (h) Effective refrigerating capacity ( $P_{\text{eff-frozen-evap}}$ ): The refrigerating capacity available to the lowest temperature evaporator when two or more evaporators are each operating in multi-temperature mode, as prescribed in paragraph 7.3.5.

### **7.2 Test procedure for multi-temperature mechanical refrigeration units**

#### **7.2.1 General procedure**

The test procedure shall be as defined in section 4 of this appendix.

The host unit shall be tested in combination with different evaporators. Each evaporator shall be tested on a separate calorimeter, if applicable.

The nominal refrigerating capacity of the host unit in mono-temperature operation, as prescribed in paragraph 7.2.2, shall be measured with a single combination of two or three evaporators including the smallest and largest.

The individual refrigerating capacity shall be measured for all evaporators, each in mono-temperature operation with the host unit, as prescribed in paragraph 7.2.3.

This test shall be conducted with two or three evaporators including the smallest, the largest and, if necessary, a mid-sized evaporator.

If the multi-temperature unit can be operated with more than two evaporators:

- The host unit shall be tested with a combination of three evaporators: the smallest, the largest and a mid-sized evaporator.
- In addition, on demand of the manufacturer, the host unit can be tested optionally with a combination of two evaporators: the largest and smallest.

The tests are done in independent mode and stand by.

#### 7.2.2 Determination of the nominal refrigerating capacity of the host unit

The nominal refrigerating capacity of the host unit in mono-temperature operation shall be measured with a single combination of two or three evaporators operating simultaneously at the same temperature. This test shall be conducted at -20°C and at 0°C.

The air inlet temperature of the host unit shall be +30°C.

The nominal refrigerating capacity at -10°C shall be calculated by linear interpolation from the capacities at -20°C and 0°C.

#### 7.2.3 Determination of the individual refrigerating capacity of each evaporator

The individual refrigerating capacity of each evaporator shall be measured in solo operation with the host unit. The test shall be conducted at -20°C and 0°C. The air inlet temperature of the refrigeration unit shall be +30°C.

The individual refrigerating capacity at -10°C shall be calculated by linear interpolation from the capacities at 0°C and -20°C.

#### 7.2.4 Test of the remaining effective refrigerating capacities of a set of evaporators in multi-temperature operation at a reference heat load

The remaining effective refrigerating capacity shall be measured for each tested evaporator at -20°C with the other evaporator(s) operating under control of a thermostat set at 0 °C with a reference heat load of 20% of the individual refrigerating capacity at -20 °C of the evaporator in question. The air inlet temperature of the host unit shall be +30 °C.

For multi-temperature refrigeration units with more than one compressor such as cascade systems or units with two-stage compression systems, where the refrigerating capacities can be simultaneously maintained in the frozen and chilled compartments, the measurement of the effective refrigerating capacity, shall be done at one additional heat load.

### **7.3 Dimensioning and certification of refrigerated multi-temperature equipment**

#### 7.3.1 General procedure

The refrigerating capacity demand of multi-temperature equipment shall be based on the refrigerating capacity demand of mono-temperature equipment as defined in this appendix.

For multi-compartment equipment, a K coefficient less than or equal to 0.40 W/m<sup>2</sup>.K for the outer body as a whole shall be approved in accordance with subsections 2 to 2.2 of this appendix.

The insulation capacities of the outer body walls shall be calculated using the K coefficient of the body approved in accordance with this Agreement. The insulation capacities of the internal dividing walls shall be calculated using the K coefficients in the table in paragraph 7.3.7.

For issuance of an ATP certificate:



- The nominal refrigerating capacity of the multi-temperature refrigeration unit shall be at least equal to the heat loss through the internal dividing and outer body walls of the equipment as a whole multiplied by the factor 1.75 as specified in paragraph 3.2.6 of this appendix.
- In each compartment, the calculated remaining effective refrigerating capacity at the lowest temperature of each evaporator in multi-temperature operation shall be greater than or equal to the maximum refrigeration demand of the compartment in the most unfavourable conditions, as prescribed in paragraphs 7.3.5 and 7.3.6, multiplied by the factor 1.75 as specified in paragraph 3.2.6 of this appendix.

### 7.3.2 Conformity of the entire body

The outer body shall have a K value  $K \leq 0.40 \text{ W/m}^2\cdot\text{K}$ .

The internal surface of the body shall not vary by more than 20 %.

The equipment shall conform to:

$$P_{\text{nominal}} > 1.75 * K_{\text{body}} * S_{\text{body}} * \Delta T$$

Where:

$P_{\text{nominal}}$  is the nominal refrigerating capacity of the multi-temperature refrigeration unit,

$K_{\text{body}}$  is the K value of the outer body,

$S_{\text{body}}$  is the internal surface of the full body,

$\Delta T$  is the difference in temperature between outside and inside the body.

### 7.3.3 Determination of the refrigerating demand of chilled evaporators

With the bulkheads in given positions, the refrigerating capacity demand of each chilled evaporator is calculated as follows:

$$P_{\text{chilled demand}} = (S_{\text{chilled-comp}} - \Sigma S_{\text{bulk}}) * K_{\text{body}} * \Delta T_{\text{ext}} + \Sigma (S_{\text{bulk}} * K_{\text{bulk}} * \Delta T_{\text{int}})$$

Where:

$K_{\text{body}}$  is the K value given by an ATP test report for the outer body,

$S_{\text{chilled-comp}}$  is the surface of the chilled compartment for the given positions of the bulkheads,

$S_{\text{bulk}}$  are the surfaces of the bulkheads,

$K_{\text{bulk}}$  are the K values of the bulkheads given by the table in paragraph 7.3.7,

$\Delta T_{\text{ext}}$  is the difference in temperatures between the chilled compartment and +30°C outside the body,

$\Delta T_{\text{int}}$  is the difference in temperatures between the chilled compartment and other compartments. For unconditioned compartments a temperature of +20°C shall be used for calculations.



#### 7.3.4 Determination of the refrigerating demand of frozen compartments

With the bulkheads in given positions, the refrigerating capacity demand of each frozen compartment is calculated as follows:

$$P_{\text{frozen demand}} = (S_{\text{frozen-comp}} - \Sigma S_{\text{bulk}}) * K_{\text{body}} * \Delta T_{\text{ext}} + \Sigma (S_{\text{bulk}} * K_{\text{bulk}} * \Delta T_{\text{int}})$$

Where:

$K_{\text{body}}$  is the K value given by an ATP test report for the outer body,

$S_{\text{frozen-comp}}$  is the surface of the frozen compartment for the given positions of the bulkheads,

$S_{\text{bulk}}$  are the surfaces of the bulkheads,

$K_{\text{bulk}}$  are the K values of the bulkheads given by the table in paragraph 7.3.7,

$\Delta T_{\text{ext}}$  is the difference in temperatures between the frozen compartment and +30 °C outside the body,

$\Delta T_{\text{int}}$  is the difference in temperatures between the frozen compartment and other compartments. For insulated compartments a temperature of +20°C shall be used for calculations.

#### 7.3.5 Determination of the effective refrigerating capacity of frozen evaporators

The effective refrigerating capacity, in given positions of the bulkheads, is calculated as follows:

$$P_{\text{eff-frozen-evap}} = P_{\text{ind-frozen-evap}} * [1 - \Sigma (P_{\text{eff-chilled-evap}} / P_{\text{ind-chilled-evap}})]$$

Where:

$P_{\text{eff-frozen-evap}}$  is the effective refrigerating capacity of the frozen evaporator with a given configuration,

$P_{\text{ind-frozen-evap}}$  is the individual refrigeration capacity of the frozen evaporator at -20 °C,

$P_{\text{eff-chilled-evap}}$  is the effective refrigeration capacity of each chilled evaporator in the given configuration as defined in paragraph 7.3.6,

$P_{\text{ind-chilled-evap}}$  is the individual refrigerating capacity at -20 °C for each chilled evaporator.

This calculation method is only approved for multi-temperature mechanical refrigeration units with a single one-stage compressor. For multi-temperature refrigeration units with more than one compressor such as cascade systems or units with two-stage compression systems, where the refrigerating capacities can be simultaneously maintained in the frozen and the chilled compartments, this calculation method shall not be used, because it will lead to an underestimation of the effective refrigerating capacities. For this equipment, the effective refrigerating capacities shall be interpolated between the effective refrigerating capacities measured with two different heat loads given in the tests reports as prescribed in 7.2.4.

7.3.6 Conformity declaration

The equipment is declared in conformity in multi-temperature operation if, for each position of the bulkheads, and each distribution of temperature in the compartments:

$$P_{\text{eff-frozen-evap}} \geq 1.75 * P_{\text{frozen demand}}$$

$$P_{\text{eff-chilled-evap}} \geq 1.75 * P_{\text{chilled demand}}$$

Where:

$P_{\text{eff-frozen-evap}}$  is the effective refrigeration capacity of the considered frozen evaporator at the class temperature of the compartment in the given configuration,

$P_{\text{eff-chilled-evap}}$  is the effective refrigeration capacity of the considered chilled evaporator at the class temperature of the compartment in the given configuration,

$P_{\text{frozen demand}}$  is the refrigerating demand of the considered compartment at the class temperature of the compartment in the given configuration as calculated according to 7.3.4,

$P_{\text{chilled demand}}$  is the refrigerating demand of the considered compartment at the class temperature of the compartment in the given configuration as calculated according to 7.3.3.

It shall be considered that all the positions of the bulkheads have been dimensioned if the wall positions from the smallest to the largest compartment sizes are checked by iterative methods whereby no input step change in surface area is greater than 20 %.

7.3.7 Internal dividing walls

Thermal losses through internal dividing walls shall be calculated using the K coefficients in the following table.

|                          | <i>K coefficient – [W/m².K]</i> |                  | <i>Minimum foam thickness</i> |
|--------------------------|---------------------------------|------------------|-------------------------------|
|                          | <i>Fixed</i>                    | <i>Removable</i> | <i>[mm]</i>                   |
| Longitudinal – alu floor | 2.0                             | 3.0              | 25                            |
| Longitudinal – GRP floor | 1.5                             | 2.0              | 25                            |
| Transversal – alu floor  | 2.0                             | 3.2              | 40                            |
| Transversal – GRP floor  | 1.5                             | 2.6              | 40                            |

K coefficients of movable dividing walls include a safety margin for specific ageing and unavoidable thermal leakages.

For specific designs with additional heat transfer caused by additional thermal bridges compared to a standard design, the partition K coefficient shall be increased.

7.3.8 The requirements of section 7 shall not apply to equipment produced before the entry into force of the requirements and having undergone equivalent tests as multi-temperature equipment. Equipment produced before the entry into force of this section may be operated in international transport but may only be transferred from one country to another with the agreement of the competent authorities of the countries concerned.

**8. TEST REPORTS**

A test report of the type appropriate to the equipment tested shall be drawn up for each test in conformity with one or other of the models 1 to 10 hereunder.



**MODEL No. 1 A**

Test Report

Prepared in conformity with the provisions of the Agreement on the International Carriage of Perishable Foodstuffs and on the Special Equipment to be Used for such Carriage (ATP)

Test report No.....

---

Section 1

Specifications of the equipment (equipment other than tanks for the carriage of liquid foodstuffs)

---

Approved testing station/expert: <sup>1</sup>

Name .....

Address .....

Type of equipment: <sup>2</sup>

Make..... Registration number..... Serial number .....

Date of first entry into service .....

Tare <sup>3</sup>.....kg Carrying capacity <sup>3</sup> .....

Body:

Make and type ..... Identification number .....

Built by.....

Owned or operated by .....

Submitted by .....

Date of construction .....

Principal dimensions:

Outside: length ..... m, width .....m, height..... m

Inside: length ..... m, width .....m, height..... m

Total floor area of body ..... m<sup>2</sup>

Usable internal volume of body ..... m<sup>3</sup>

**MODEL No. 1 A (cont'd)**

Total inside surface area  $S_i$  of body ..... m<sup>2</sup>

Total outside surface area  $S_e$  of body ..... m<sup>2</sup>

Mean surface area:  $S = \sqrt{S_i \cdot S_e}$  ..... m<sup>2</sup>

Specifications of the body walls: <sup>4</sup>

Top .....

Bottom .....

Sides .....

Structural peculiarities of body: <sup>5</sup>

Number, ( ) of doors .....

positions ( ) of vents .....

and dimensions ( ) of ice-loading apertures.....

Accessories <sup>6</sup> .....  
.....

K coefficient = ..... W/m<sup>2</sup>.K

---

---

<sup>1</sup> Delete as necessary (experts only in the case of tests carried out under ATP Annex 1, Appendix 2, sections 5 or 6).

<sup>2</sup> Wagon, lorry, trailer, semi-trailer, container, etc.

<sup>3</sup> State source of information.

<sup>4</sup> Nature and thickness of materials constituting the body walls, from the interior to the exterior, mode of construction, etc.

<sup>5</sup> If there are surface irregularities, show how  $S_i$  and  $S_e$  were determined.

<sup>6</sup> Meat bars, flettner fans, etc.

**MODEL No. 1 B**

Test Report

Prepared in conformity with the provisions of the Agreement on the International Carriage of  
Perishable Foodstuffs and on the Special Equipment to be Used for such Carriage (ATP)

Test report No.....

---

Section 1

Specifications of tanks for the carriage of liquid foodstuffs

---

Approved testing station/expert: <sup>1</sup>

Name .....

Address .....

Type of tank: <sup>2</sup>

Make ..... Registration number ..... Serial number .....

Date of first entry into service .....

Tare <sup>3</sup> ..... kg Carrying capacity <sup>3</sup> ..... kg

Tank:

Make and type ..... Identification number .....

Built by .....

Owned or operated by .....

Submitted by .....

Date of construction .....

Principal dimensions:

Outside: length of cylinder .....m, major axis ..... m, minor axis ..... m

Inside: length of cylinder ..... m, major axis ..... m, minor axis ..... m

Usable internal volume ..... m<sup>3</sup>

**MODEL No. 1 B (cont'd)**

|  |                |
|--|----------------|
| Internal volume of each compartment .....  | m <sup>3</sup> |
| Total inside surface area S <sub>i</sub> of tank .....                               | m <sup>2</sup> |
| Inside surface area of each compartment S <sub>i1</sub> ....., S <sub>i2</sub> ..... | m <sup>2</sup> |
| Total outside surface area S <sub>e</sub> of tank .....                              | m <sup>2</sup> |
| Mean surface area of tank: $S = \sqrt{S_i \cdot S_e}$ .....                          | m <sup>2</sup> |
| Specifications of the tank walls: <sup>4</sup> .....                                 |                |
| Structural peculiarities of the tank: <sup>5</sup> .....                             |                |
| Number, dimensions and description of manholes .....                                 |                |
| Description of manhole covers .....  |                |
| Number, dimensions and description of discharge piping .....                         |                |
| Number and description of tank cradles .....   |                |
| Accessories .....  |                |

---

---

<sup>1</sup> Delete as necessary (experts only in the case of tests carried out under ATP Annex 1, Appendix 2, sections 5 or 6).  
<sup>2</sup> Wagon, lorry, trailer, semi-trailer, container, etc.  
<sup>3</sup> State source of information.  
<sup>4</sup> Nature and thickness of materials constituting the tank walls, from the interior to the exterior, mode of construction, etc.  
<sup>5</sup> If there are surface irregularities, show how S<sub>i</sub> and S<sub>e</sub> were determined.

**MODEL No. 2 A**

Section 2

Measurement in accordance with ATP, Annex 1, Appendix 2, sub-section 2.1, of the overall coefficient of heat transfer of equipment other than tanks for liquid foodstuffs

---

Testing method: inside cooling/inside heating <sup>1</sup>

Date and time of closure of equipment's doors and other openings: .....

Averages obtained for ..... hours of continuous operation  
(from ..... a.m./p.m. to ..... a.m./p.m.):

(a) Mean outside temperature of body:  $T_e = \dots\dots\dots^\circ\text{C} \pm \dots\dots\dots\text{K}$

(b) Mean inside temperature of body:  $T_i = \dots\dots\dots^\circ\text{C} \pm \dots\dots\dots\text{K}$

(c) Mean temperature difference achieved:  $\Delta T = \dots\dots\dots\text{K}$

Maximum temperature spread:

Outside body .....K

Inside body .....K

Mean temperature of walls of body  $\frac{T_e + T_i}{2}$  ..... °C

Operating temperature of heat exchanger <sup>2</sup> ..... °C

Dew point of atmosphere outside body during continuous operation <sup>2</sup>  
..... °C ± .....K

Total duration of test .....h

Duration of continuous operation .....h

Power consumed in exchangers:  $W_1$  ..... W

Power absorbed by fans:  $W_2$  ..... W

Overall coefficient of heat transfer calculated by the formula:

Inside-cooling test <sup>1</sup>       $K = \frac{W_1 - W_2}{S \cdot \Delta T}$

Inside-heating test <sup>1</sup>       $K = \frac{W_1 + W_2}{S \cdot \Delta T}$

$K = \dots\dots\dots \text{W/m}^2\cdot\text{K}$



**MODEL No. 2 A (cont'd)**

Maximum error of measurement with test used ..... %

Remarks: <sup>3</sup> .....

---

(To be completed only if the equipment does not have thermal appliances:)

According to the above test results, the equipment may be recognized by means of a certificate in accordance with ATP Annex 1, Appendix 3, valid for a period of not more than six years, with the distinguishing mark IN/IR.<sup>1</sup>

However, this report shall be valid as a certificate of type approval within the meaning of ATP Annex 1, Appendix 1, paragraph 6 (a) only for a period of not more than six years, that is until .....

Done at: .....

on .....

.....

Testing Officer

---

<sup>1</sup> Delete as necessary.

<sup>2</sup> For inside-cooling test only.

<sup>3</sup> If the body is not parallelepipedic, specify the points at which the outside and inside temperatures were measured.

**MODEL No. 2 B**

Section 2

Measurement, in accordance with ATP Annex 1, Appendix 2, sub-section 2.2, of the overall coefficient of heat transfer of tanks for liquid foodstuffs

---

Testing method: inside heating

Date and time of closure of equipment's openings .....

Mean values obtained for .....hours of continuous operation

(from ..... a.m./p.m. to ..... a.m./p.m.):

(a) Mean outside temperature of tank:  $T_e = \dots\dots\dots^\circ\text{C} \pm \dots\dots\dots\text{K}$

(b) Mean inside temperature of tank:

$$T_i = \frac{\sum S_{in} \cdot T_{in}}{\sum S_{in}} = \dots\dots\dots^\circ\text{C} \pm \dots\dots\dots\text{K}$$

(c) Mean temperature difference achieved:  $\Delta T \dots\dots\dots\text{K}$

Maximum temperature spread:

Inside tank .....K

Inside each compartment .....K

Outside tank .....K

Mean temperature of tank walls ..... $^\circ\text{C}$

Total duration of test .....h

Duration of continuous operation .....h

Power consumed in exchangers:  $W_1 \dots\dots\dots\text{W}$

Power absorbed by fans:  $W_2 \dots\dots\dots\text{W}$

Overall coefficient of heat transfer calculated by the formula:

$$K = \frac{W_1 + W_2}{S \cdot \Delta T}$$

$K = \dots\dots\dots\text{W/m}^2\cdot\text{K}$

**MODEL No. 2 B (cont'd)**

Maximum error of measurement with test used ..... %

Remarks: <sup>1</sup> .....  
.....

---

(To be completed only if the equipment does not have thermal appliances:)

According to the above test results, the equipment may be recognized by means of a certificate in accordance with ATP Annex 1, Appendix 3, valid for a period of not more than six years, with the distinguishing mark IN/IR. <sup>2</sup>

However, this report shall be valid as a certificate of type approval within the meaning of ATP Annex 1, Appendix 1, paragraph 6 (a) only for a period of not more than six years, that is until .....

Done at:.....

on: .....

Testing Officer

---

<sup>1</sup> *If the tank is not parallelepipedic, specify the points at which the outside and inside temperatures were measured.*

<sup>2</sup> *Delete as necessary.*

**MODEL No. 3**

Section 2

Expert field check of the insulating capacity of equipment in service in accordance with  
ATP Annex 1, Appendix 2, section 5

---

The check was based on test report No..... dated .....  
issued by approved testing station expert (name and address).....  
.....

Condition when checked:

Top .....

Side walls .....

End wall .....

Bottom .....

Doors and openings .....

Seals .....

Cleaning drainholes .....

Air tightness .....

K coefficient of the equipment when new (as shown in the previous test report) .....  
.....W/m<sup>2</sup>.K

Remarks: .....  
.....

---

According to the above test results the equipment may be recognized by means of a certificate in  
accordance with ATP Annex 1, Appendix 3, valid for not more than three years, with the  
distinguishing mark IN/IR.<sup>1</sup>

Done at .....

on: .....  
Testing Officer

---

<sup>1</sup> Delete as necessary.

**MODEL No. 4 A**

Section 3

Determination of the efficiency of cooling appliances of refrigerated equipment using ice or dry ice by an approved testing station in accordance with ATP Annex 1, Appendix 2, sub-section 3.1, except 3.1.3 (b) and 3.1.3 (c)

---

Cooling appliance:

Description of cooling appliance .....  
Nature of refrigerant .....  
Nominal refrigerant filling capacity specified  
by manufacturer .....kg  
Actual filling of refrigerant used for test .....kg  
Drive independent/dependent/mains-operated <sup>1</sup> .....  
Cooling appliance removable/not removable <sup>1</sup> .....  
Manufacturer .....  
Type, serial number .....  
Year of manufacture .....  
Filling device (description, where situated;  
attach drawing if necessary) .....  
.....

Inside ventilation appliances:

Description (number of appliances, etc.) .....  
Power of electric fans ..... W  
Delivery rate ..... m<sup>3</sup>/h  
Dimensions of ducts: cross-section ..... m<sup>2</sup>, length ..... m  
Air intake screen; description <sup>1</sup> .....

---

<sup>1</sup> Delete if not applicable.

**MODEL No. 4 A (cont'd)**

Automatic devices .....

Mean temperatures at beginning of test:

Inside .....°C ± .....K

Outside .....°C ± .....K

Dew point in test chamber .....°C ± .....K

Power of internal heating system ..... W

Date and time of closure of equipment's doors and other openings .....

Record of mean inside and outside temperatures of body and/or curve showing variation of these temperatures with time .....

Remarks: .....  
.....

---

According to the above test results, the equipment may be recognized by means of a certificate in accordance with ATP Annex 1, Appendix 3, valid for a period of not more than six years, with the distinguishing mark .....

However, this report shall be valid as a certificate of type approval within the meaning of ATP Annex 1, Appendix 1, paragraph 6 (a) only for a period of not more than six years, that is until .....

Done at: .....

on: ..... .....

Testing Officer

**MODEL No. 4 B**

Section 3

Determination of the efficiency of cooling appliances of refrigerated equipment with eutectic plates by an approved testing station in accordance with ATP Annex 1, Appendix 2, sub-section 3.1, except 3.1.3 (a) and 3.1.3 (c)

---

Cooling appliance:

Description .....

Nature of eutectic solution .....

Nominal eutectic solution filling capacity specified  
by manufacturer ..... kg

Latent heat at freezing temperature stated by manufacturer .....kJ/kg at ..... °C

Cooling appliance removable/not removable <sup>1</sup>

Drive independent/dependent/mains-operated <sup>1</sup>

Manufacturer .....

Type, serial number .....

Year of manufacture .....

Eutectic plates: Make ..... Type .....

Dimensions and number of plates, where situated;  
distance from walls (attach drawing) .....

.....

Total cold reserve stated by manufacturer for freezing  
temperature of .....kJ to .....°C

Inside ventilation appliances (if any):

Description .....

Automatic devices .....

---

<sup>1</sup> Delete if not applicable.

**MODEL No. 4 B (cont'd)**

Mechanical refrigerator (if any):

Make .....Type .....No.....

Where situated .....

Compressor: Make .....Type .....

Type of drive .....

Nature of refrigerant .....

Condenser .....

Refrigerating capacity stated by the manufacturer for the specified freezing temperature and an outside temperature of + 30 °C .....W

Automatic devices:

Make .....Type .....

Defrosting (if any) .....

Thermostat .....

LP pressostat .....

HP pressostat .....

Relief valve .....

Others.....

Accessory devices:

Electrical heating devices of the door joint:

Capacity by linear metre of the resistor .....W/m

Linear length of the resistor .....m

Mean temperatures at beginning of test:

Inside .....°C ± .....K

Outside .....°C ± .....K

Dew point in test chamber .....°C ± .....K



**MODEL No. 4 B (cont'd)**

Power of internal heating system ..... W

Date and time of closure of equipment's  
doors and openings .....

Period of accumulation of cold .....h

Record of mean inside and outside temperatures of body  
and/or curve showing variation of these temperatures  
with time .....

.....

Remarks: .....

.....

---

According to the above test results, the equipment may be recognized by means of a certificate in  
accordance with ATP Annex 1, Appendix 3, valid for a period of not more than six years, with the  
distinguishing mark .....

However, this report shall be valid as a certificate of type approval within the meaning of ATP  
Annex 1, Appendix 1, paragraph 6 (a) only for a period of not more than six years, that is until  
.....

Done at: .....

on: ..... .....

Testing Officer

**MODEL No. 4 C**

Section 3

Determination of the efficiency of cooling appliances of refrigerated equipment using liquefied gases by an approved testing station in accordance with ATP Annex 1, Appendix 2, sub-section 3.1, except 3.1.3 (a) and 3.1.3 (b)

---

Cooling appliance:

Description .....

Drive independent/dependent/mains-operated <sup>1</sup>

Cooling appliance removable/not removable <sup>1</sup>

Manufacturer .....

Type, serial number .....

Year of manufacture .....

Nature of refrigerant .....

Nominal refrigerant filling capacity specified  
by manufacturer .....kg

Actual filling of refrigerant used for test .....kg

Description of tank.....

Filling device (description, where situated) .....

Inside ventilation appliances:

Description (number, etc.) .....

Power of electric fans ..... W

Delivery rate ..... m<sup>3</sup>/h

Dimensions of ducts: cross-section ..... m<sup>2</sup>, length ..... m

Automatic devices .....

---

<sup>1</sup> Delete if not applicable.

**MODEL No. 4 C (cont'd)**

Mean temperatures at beginning of test:

Inside .....°C ± .....K

Outside .....°C ± .....K

Dew point in test chamber .....°C ± .....K

Power of internal heating system .....W

Date and time of closure of equipment's  
doors and openings .....

Record of mean inside and outside temperatures of body and/or curve showing  
variation of these temperatures with time .....

.....

Remarks: .....

.....

---

According to the above test results, the equipment may be recognized by means of a certificate in  
accordance with ATP Annex 1, Appendix 3, valid for a period of not more than six years, with the  
distinguishing mark .....

However, this report shall be valid as a certificate of type approval within the meaning of ATP  
Annex 1, Appendix 1, paragraph 6 (a), only for a period of not more than six years, that is until  
.....

Done at: .....

on: ..... .....

Testing Officer

**MODEL No. 5**

Section 3

Determination of the efficiency of cooling appliances of mechanically refrigerated equipment by an approved testing station in accordance with ATP Annex 1, Appendix 2, sub-section 3.2

---

Mechanical refrigerating appliances:

Drive independent/dependent/mains-operated <sup>1</sup>

Mechanical refrigerating appliances removable/not removable <sup>1</sup>

Manufacturer .....

Type, serial number .....

Year of manufacture .....

Nature of refrigerant and filling capacity .....

Effective refrigerating capacity stated by manufacturer for an outside temperature of + 30 °C and an inside temperature of:

0 °C ..... W

-10 °C ..... W

-20 °C ..... W

Compressor:

Make ..... Type .....

Drive: electric/thermal/hydraulic <sup>1</sup>

Description .....

Make ..... Type ..... power .....kW at .....rpm

Condenser and evaporator .....

Motor element of fan(s): make ..... type ..... number .....

power ..... kW at ..... rpm

Inside ventilation appliances:

Description (number of appliances, etc.) .....

Power of electric fans ..... W

Delivery rate ..... m<sup>3</sup>/h

Dimensions of ducts: cross-section ..... m<sup>2</sup>, length ..... m

---

<sup>1</sup> Delete if not applicable.

**MODEL No. 5 (cont'd)**

Automatic devices:

Make ..... Type .....  
Defrosting (if any) .....  
Thermostat .....  
LP pressostat .....  
HP pressostat .....  
Relief valve .....  
Others.....

Mean temperatures at beginning of test:

Inside temperature ..... °C ± ..... K  
Outside temperature ..... °C ± ..... K  
Dew point in test chamber ..... °C ± ..... K

Power of internal heating system ..... W

Date and time of closure of equipment's  
doors and other openings .....

Record of mean inside and outside temperatures of body and/or curve showing variation  
of these temperatures with time .....

Time between beginning of test and attainment  
of prescribed mean inside temperature of body .....h

Remarks: .....

---

According to the above test results, the equipment may be recognized by means of a certificate in  
accordance with ATP Annex 1, Appendix 3, valid for a period of not more than six years, with the  
distinguishing mark .....

However, this report shall be valid as a certificate of type approval within the meaning of ATP  
Annex 1, Appendix 1, paragraph 6 (a), only for a period of not more than six years, that is until  
.....

Done at: .....

on: .....

.....

Testing Officer

**MODEL No. 6**

Section 3

Determination of the efficiency of heating appliances of heated equipment by an approved testing station in accordance with ATP Annex 1, Appendix 2, sub-section 3.3

---

Heating appliance:

Description .....

Drive independent/dependent/mains-operated <sup>1</sup>

Heating appliance removable/not removable <sup>1</sup>

Manufacturer .....

Type, serial number .....

Year of manufacture .....

Where situated .....

Overall area of heat exchange surfaces ..... m<sup>2</sup>

Effective power rating as specified by manufacturer ..... kW

Inside ventilation appliances:

Description (number of appliances, etc.) .....

Power of electric fans..... W

Delivery rate ..... m<sup>3</sup>/h

Dimensions of ducts: cross-section ..... m<sup>2</sup>, length ..... m

Mean temperatures at beginning of test:

Inside temperature ..... °C ± ..... K

Outside temperature ..... °C ± ..... K

Date and time of closure of equipment's doors and other openings .....

---

<sup>1</sup> Delete if not applicable.

**MODEL No. 6 (cont'd)**

Record of mean inside and outside temperatures of body and/or curve showing variation of these temperatures with time .....

.....

Time between beginning of test and attainment of prescribed mean inside temperature of body .....h

Where applicable, mean heating output during test to maintain prescribed temperature difference <sup>2</sup> between inside and outside of body..... W

Remarks: .....

.....

---

According to the above test results, the equipment may be recognized by means of a certificate in accordance with ATP Annex 1, Appendix 3, valid for a period of not more than six years, with the distinguishing mark .....

However, this report shall be valid as a certificate of type approval within the meaning of ATP Annex 1, Appendix 1, paragraph 6 (a), only for a period of not more than six years, that is until .....

Done at: .....

on: .....

Testing Officer

---

<sup>2</sup> *Increased by 35% for new equipment.*

**MODEL No. 7**

Section 3

Expert field check of the efficiency of cooling appliances of refrigerated equipment in service in accordance with ATP Annex 1, Appendix 2, sub-section 6.1

---

The check was conducted on the basis of report No .....  
dated ....., issued by approved  
testing station/expert (name, address) .....

Cooling appliance:

Description .....

Manufacturer .....

Type, serial number .....

Year of manufacture .....

Nature of refrigerant .....

Nominal refrigerant filling capacity  
specified by manufacturer .....kg

Actual filling of refrigerant used for test .....kg

Filling device (description, where situated) .....

Inside ventilation appliances:

Description (number of appliances, etc.) .....

Power of electric fans ..... W

Delivery rate ..... m<sup>3</sup>/h

Dimensions of ducts: cross-section ..... m<sup>2</sup>, length .....m

Condition of cooling appliance and ventilation appliances .....

.....

.....

Inside temperature attained ..... °C

At an outside temperature of ..... °C



**MODEL No. 7 (cont'd)**

Inside temperature of the equipment before the refrigerating appliance is started ..... °C

Total running time of the refrigerating unit .....h

Time between beginning of test and attainment of prescribed mean inside temperature of body .....h

Check on operation of thermostat .....

For refrigerated equipment with eutectic plates:

Period of operation of the cooling appliance for freezing of the eutectic solution .....h

Period during which inside air temperature is maintained after the appliance is switched off .....h

Remarks: .....

.....

---

According to the above test results, the equipment may be recognized by means of a certificate in accordance with ATP Annex 1, Appendix 3, valid for a period of not more than three years, with the distinguishing mark .....

Done at: .....

on: .....

Testing Officer

**MODEL No. 8**

Section 3

Expert field check of the efficiency of cooling appliances of mechanically refrigerated equipment in service in accordance with ATP Annex 1, Appendix 2, sub-section 6.2

---

The check was conducted on the basis of report No..... dated .....  
issued by approved testing station/expert (name, address) .....  
.....

Mechanical refrigerating appliances:

Manufacturer .....

Type, serial number .....

Year of manufacture .....

Description .....

Effective refrigerating capacity specified by manufacturer for an outside temperature of +30 °C and an inside temperature of

0 °C ..... W

-10 °C ..... W

-20 °C ..... W

Nature of refrigerant and filling capacity .....kg

Inside ventilation appliances:

Description (number of appliances, etc.) .....

Power of electric fans ..... W

Delivery rate .....m<sup>3</sup>/h

Dimensions of ducts: cross-section ..... m<sup>2</sup>, length .....m

Condition of mechanical refrigerating appliance and inside ventilation appliances .....  
.....

**MODEL No. 8 (cont'd)**

Inside temperature attained ..... °C

At an outside temperature of ..... °C

and with a relative running time of ..... %

Running time .....h

Check on operation of thermostat .....

Remarks: .....

.....

---

According to the above test results, the equipment may be recognized by means of a certificate in accordance with ATP Annex 1, Appendix 3 valid for a period of not more than three years, with the distinguishing mark .....

Done at: .....

on: ..... .....

Testing Officer

**MODEL No. 9**

Section 3

Expert field check of the efficiency of heating appliances of heated equipment in service in accordance with ATP Annex 1, Appendix 2, sub-section 6.3

---

The check was conducted on the basis of report No. .... dated .....  
issued by approved testing station/expert (name, address) .....  
.....

Mode of heating:

Description .....

Manufacturer .....

Type, serial number .....

Year of manufacture .....

Where situated .....

Overall area of heat exchange surfaces ..... m<sup>2</sup>

Effective power rating as specified by manufacturer ..... kW

Inside ventilation appliances:

Description (number of appliances, etc.) .....

Power of electric fans ..... W

Delivery rate ..... m<sup>3</sup>/h

Dimensions of ducts: cross-section ..... m<sup>2</sup>, length ..... m

Condition of heating appliance and inside ventilation appliances .....  
.....  
.....

Inside temperature attained ..... °C

**MODEL No. 9 (cont'd)**

At an outside temperature of ..... °C

and with a relative running time of ..... %

Running time .....h

Check on operation of thermostat .....

Remarks: .....

.....

---

According to the above test results, the equipment may be recognized by means of a certificate in accordance with ATP Annex 1, Appendix 3, valid for a period of not more than three years, with the distinguishing mark .....

Done at: .....

on: ..... Testing Officer

**MODEL No. 10**

**TEST REPORT**

Prepared in conformity with the provisions of the Agreement on the International Carriage of Perishable Foodstuffs and on the Special Equipment to be Used for such Carriage (ATP)

Test Report No.....

Determination of the effective refrigerating capacity of a refrigeration unit  
in accordance with section 4 of ATP Annex 1, Appendix 2

---

Approved testing station

Name: .....

Address: .....

Refrigeration unit presented by: .....

.....

.....

(a) Technical specifications of the unit

Date of manufacture: ..... Make: .....

Type: ..... Serial No: .....

Category <sup>1</sup>

Self-contained/not self-contained

Removable/not removable

Single unit/assembled components

Description: .....

.....

.....

Compressor: Make: ..... Type: .....

Number of cylinders: ..... Cubic capacity: .....

Nominal speed of rotation: ..... rpm

Methods of drive <sup>1</sup>: electric motor, separate internal combustion engine,  
vehicle engine, vehicle motion

Compressor drive motor: <sup>1,2</sup>

Electrical: Make: ..... Type: .....

Power: .....kW at ..... rpm

Supply voltage .....V Supply frequency ..... Hz

**MODEL No. 10 (cont'd)**

Internal combustion engine: Make: ..... Type: .....  
 Number of cylinders: ..... Cubic capacity: .....  
 Power:..... kW at .....rpm  
 Fuel: .....

Hydraulic motor: Make: ..... Type: .....  
 Method of drive:.....

Alternator: Make: ..... Type:.....  
 Method of drive:.....

Speed of rotation: (nominal speed given by the manufacturer:  
 ( .....rpm  
 ( .....rpm  
 (minimum speed: .....rpm

Refrigerant fluid: .....

| Heat exchangers                                       |  | Condenser | Evaporator |
|---|--|-----------|------------|
| Make-type   |  |           |            |
| Number of tubes                                       |  |           |            |
| Fan pitch (mm) <sup>2/</sup>                          |  |           |            |
| Tube: nature and diameter (mm) <sup>2/</sup>          |  |           |            |
| Exchange surface area (m <sup>2</sup> ) <sup>2/</sup> |  |           |            |
| Frontal area (m <sup>2</sup> )                        |  |           |            |
| FANS  | Number   |           |            |
|   | Number of blades per fan   |           |            |
|   | Diameter (mm)  |           |            |
|   | Nominal power (W) <sup>2/,3/</sup>   |           |            |
|   | Total nominal output at a pressure of . . . . . Pa (m <sup>3</sup> /h) <sup>2/</sup> |           |            |
|   | Method of drive  |           |            |

Expansion valve: Make: ..... Model: .....

Adjustable: <sup>1</sup> ..... Not adjustable: <sup>1</sup> .....

Defrosting device: .....

Automatic device: .....

**MODEL No.10 (cont'd)**

Results of measurements and refrigerating performance

(Mean temperature of the air to the inlet(s) of the refrigeration unit . . . . . °C)

|  |                         |           |         |       |       |       |         |       |       |  |
|--|-------------------------|-----------|---------|-------|-------|-------|---------|-------|-------|--|
| Effective refrigerating capacity                   |                         | W         | .....   | ..... | ..... | ..... | .....   | ..... | ..... |  |
| Internal temperature                               | Inlet to evaporator     | °C        | .....   | ..... | ..... | ..... | .....   | ..... | ..... |  |
|  | Mean                    | °C        | .....   | ..... | ..... | ..... | .....   | ..... | ..... |  |
| Mean temperature around the body                   |                         | °C        | .....   | ..... | ..... | ..... | .....   | ..... | ..... |  |
| Fuel or electrical power consumption               |                         | W or l/hr | .....   | ..... | ..... | ..... | .....   | ..... | ..... |  |
| Power absorbed by the unit cooler fan <sup>4</sup> |                         | W         | .....   | ..... | ..... | ..... | .....   | ..... | ..... |  |
| Power of internal fan heater                       |                         | W         | .....   | ..... | ..... | ..... | .....   | ..... | ..... |  |
| Speed of rotation                                  | Compressor <sup>3</sup> | rpm       | .....   | ..... | ..... | ..... | .....   | ..... | ..... |  |
|  | Alternator <sup>3</sup> | rpm       | .....   | ..... | ..... | ..... | .....   | ..... | ..... |  |
|  | Fans <sup>3</sup>       | rpm       | .....   | ..... | ..... | ..... | .....   | ..... | ..... |  |
|  |                         |           |         |       |       |       |         |       |       |  |
|  |                         |           | Nominal |       |       |       | Minimal |       |       |  |



**MODEL No. 10 (cont'd)**

(b) Test method and results:

Test method <sup>1</sup>: heat balance method/enthalpy difference method

In a calorimeter box of mean surface area = ..... m<sup>2</sup>  
measured value of the U-coefficient of a box  
fitted with a refrigeration unit: .....W/°C,  
at a mean wall temperature of .....°C.

In an item of transport equipment:  
measured value of the U-coefficient of an item of transport equipment fitted with a  
refrigeration unit: .....W/°C,  
at a mean wall temperature of .....°C.

Method employed for the correction of the U-coefficient of the body as a function of the mean wall  
temperature of the body: .....  
.....  
.....

Maximum errors of determination of:

U-coefficient of the body .....  
refrigerating capacity of the unit .....

(c) Checks

Temperature regulator: Setting .....°C Differential .....°C

Functioning of the defrosting device <sup>1</sup>: satisfactory/unsatisfactory

Air flow volume leaving the evaporator: value measured .....m<sup>3</sup>/h  
at a pressure of .....Pa

Existence of a means of supplying heat to the evaporator for setting the thermostat between 0 and  
12 °C <sup>1</sup>: yes/no

(d) Remarks

.....  
.....  
.....

Done at: .....

On: .....

Testing Officer

---

<sup>1</sup> Delete where applicable.  
<sup>2</sup> Value indicated by the manufacturer.  
<sup>3</sup> Where applicable.  
<sup>4</sup> Enthalpy difference method only.

**Annex 1, Appendix 3**

**A. Model form of certificate of compliance of the equipment, as prescribed  
in Annex 1, Appendix 1, paragraph 3**

**FORM OF CERTIFICATE FOR INSULATED, REFRIGERATED, MECHANICALLY  
REFRIGERATED OR HEATED EQUIPMENT USED FOR THE INTERNATIONAL  
CARRIAGE OF PERISHABLE FOODSTUFFS BY LAND**

Certificates of compliance of equipment issued before 2 January 2011 in accordance with the requirements regarding the model of the certificate in Annex 1, Appendix 3 in force until 1 January 2011 shall remain valid until their original date of expiry.

Certificates of compliance issued before the date of entry into force of the modification to item 3 of the model certificate (30 September 2015) shall remain valid until their original date of expiry.

XXXXXXXXXX<sup>3</sup>

XXXXXXXXXX / EQUIPMENT<sup>1</sup>  
INSULATED REFRIGERATED MECHANICALLY REFRIGERATED HEATED MULTI-TEMPERATURE<sup>4</sup>

XXXXXXXXXX / CERTIFICATE<sup>5</sup> ATP XXXXXXXXXXXX

Foodstuffs and on the Special Equipment to be Used for such Carriage (ATP) / Issued pursuant to the Agreement on the International Carriage of Perishable

1. XX / Issuing authority:  
2. XX / Equipment<sup>6</sup>:  
3. XXXXXXXXXXXXX XXXXXXXXXXXXX / Vehicle identification number<sup>a</sup> XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX  
/ Registration number<sup>a</sup>:

XXX / allotted by:  
Insulated box: MARK, MODEL, SERIAL NUMBER, XX  
MONTH AND YEAR OF MANUFACTURE<sup>15</sup>  
4. XX  
XXX  
Owner or operated by:

5. XX / Submitted by:  
6. XX / Is approved as:<sup>7</sup>

6.1. XX / With one or more thermal appliances which is (are)<sup>1</sup>:  
6.1.1. XX / Independent;<sup>8</sup> MARK, MODEL, REFRIGERANT, SERIAL NUMBER/YEAR OF MANUFACTURE (If any)  
6.1.2. XX / Not independent;<sup>8</sup> MARK, MODEL, REFRIGERANT, SERIAL NUMBER/YEAR OF MANUFACTURE (If any)  
6.1.3. XX / Removable;  
6.1.4. XX / Not removable.

7. XX / Basis of issue of certificate:  
7.1. XX / This certificate is issued on the basis of:<sup>1</sup>  
7.1.1. XX / Tests of the equipment;  
7.1.2. XX / conformity with a reference item of equipment;  
7.1.3. XX / A periodic inspection.

7.2. XX / Specify:  
7.2.1. XX / The testing station:  
7.2.2. XX / The nature of the tests:<sup>9</sup>  
7.2.3. XX / The number(s) of the report(s):

NNNNNNNN (TESTING STATION) YYYY/MM/DD and NNNNNNNN (TESTING STATION) YYYY/MM/DD

7.2.4. XX / The K coefficient: **0.nn W/m<sup>2</sup>K**  
7.2.5. XX / The effective refrigerating capacity at an  
outside temperature of 30 °C and an inside temperature of:<sup>10</sup>

| 11 | Nominal capacity | Evap.1 | Evap.2 | Evap.3 |
|----|------------------|--------|--------|--------|
| °C | XXXX W           | XXXX W | XXXX W | XXXX W |
| °C | XXXX W           | XXXX W | XXXX W | XXXX W |
| °C | XXXX W           | XXXX W | XXXX W | XXXX W |

7.3. XX / Number of openings and special equipment X  
7.3.1. XX / Number of doors: X / rear door X / side door(s) X  
7.3.2. XX / Number of vents: X  
7.3.3. XX / Hanging meat equipment: X  
/ Others X  
8. XX / This certificate is valid until: MONTH & YEAR  
8.1. XX / Provided that:  
8.1.1. XX / The insulated body and,

where applicable, the thermal appliance is maintained in good condition; and  
8.1.2. XX / No material alteration is made to the thermal appliances;

9. XX / Done by:  
XXX  
XXX  
XXX  
10. XX / On: YYYY/MM/DD

**CERTIFIED DUPLICATE<sup>12</sup>**  
Do not print this stamp on the original Certificate  
(Officer name)  
(Competent or authorized authority)

**LOGOTYPE<sup>13</sup>**  
Security stamp (relief,  
ultraviolet, etc.)  
XXXXXXXXXXXXXXXXXXXXXXXXXXXX  
Original document

XXX / The competent authority  
XXX  
XXX / Responsible for the ATP  
14  
  
(Officer name)

a XX / Not mandatory

---

*These footnotes shall not be printed on the certificate itself.*

*The areas in grey shall be replaced by the translation in the language of the country issuing the ATP Certificate.*

<sup>1</sup> *Strike out what does not apply.*

<sup>2</sup> *Distinguishing sign of the country, as used in international road traffic.*

<sup>3</sup> *The number (figures, letters, etc.) indicating the authority issuing the certificate and the approval reference.*

<sup>4</sup> *The test procedure for new multi-temperature equipment appears in section 7 of annex 1, appendix 2. A test procedure for in-service multi-temperature equipment has not yet been determined. Multi-temperature equipment is insulated equipment with two or more compartments for different temperatures in each compartment.*

<sup>5</sup> *The blank certificate shall be printed in the language of the issuing country and in English, French or Russian; the various items shall be numbered as in the above model.*

<sup>6</sup> *State type (wagon, lorry, trailer, semi-trailer, container, etc.); in the case of tank equipment for carriage of liquid foodstuffs, add the word "tank".*

<sup>7</sup> *Enter here one or more of the descriptions listed in Appendix 4 of Annex 1, together with the corresponding distinguishing mark or marks.*

<sup>8</sup> *Write the mark, model, refrigerant, serial number and year of manufacture of the equipment.*

<sup>9</sup> *Measurement of the overall coefficient of heat transfer, determination of the efficiency of cooling appliances, etc.*

<sup>10</sup> *Where determined in conformity with the provisions of Appendix 2, paragraph 3.2.7, of this Annex.*

<sup>11</sup> *The effective cooling capacity of each evaporator depends on the number of evaporators fixed at the condensing unit.*

<sup>12</sup> *In case of loss, a new Certificate can be provided or, instead of it, a photocopy of the ATP Certificate bearing a special stamp with "CERTIFIED DUPLICATE" (in red ink) and the name of the certifying officer, his signature, and the name of the competent authority or authorized body.*


<sup>13</sup> *Security stamp (relief, fluorescent, ultraviolet, or other safety mark that certifies the origin of the certificate).*

<sup>14</sup> *If applicable, mention the way the power for issuing ATP Certificates is delegated.*

<sup>15</sup> *Write the mark, model, serial number of the manufacturer and month and year of manufacture of the insulated body. All the serial numbers of insulated equipment (containers) having an internal volume of less than 2m<sup>3</sup> shall be listed. It is also acceptable to collectively list these numbers, i.e. from number ... to number ....*

**B. Certification plate of compliance of the equipment, as provided for  
in Annex 1, Appendix 1, paragraph 3**

1. The certification plate shall be affixed to the equipment permanently and in a clearly visible place adjacent to any other approval plate issued for official purposes. The plate, conforming to the model reproduced below, shall take the form of a rectangular, corrosion-resistant and fire-resistant plate measuring at least 160 mm by 100 mm. The following particulars shall be indicated legibly and indelibly on the plate in at least the English or French or Russian language:
  - (a) The Latin letters "ATP" followed by the words "APPROVED FOR TRANSPORT OF PERISHABLE FOODSTUFFS";
  - (b) "APPROVAL NUMBER" followed by the distinguishing sign (in international road traffic) of the State in which the approval was granted and the number (figures, letters, etc.) of the approval reference;
  - (c) "EQUIPMENT NUMBER" followed by the individual number assigned to identify the particular item of equipment (which may be the manufacturer's number);
  - (d) "ATP MARK" followed by the distinguishing mark prescribed in annex 1, appendix 4, corresponding to the class and the category of the equipment;
  - (e) "VALID UNTIL" followed by the date (month and year) when the approval of the unit of equipment expires. If the approval is renewed following a test or inspection, the subsequent date of expiry may be added on the same line.
2. The letters "ATP" and the letters of the distinguishing mark should be approximately 20 mm high. Other letters and figures should not be less than 5 mm high.



\* The particulars in square brackets are given by way of example.



## Annex I, Appendix 4

### **DISTINGUISHING MARKS TO BE AFFIXED TO SPECIAL EQUIPMENT**

The distinguishing marks prescribed in appendix 1, paragraph 4 to this annex shall consist of capital Latin letters in dark blue on a white ground. The height of the letters shall be at least 100 mm for the classification marks and at least 50 mm for the expiry dates. For special equipment, such as a laden vehicle with maximum mass not exceeding 3.5 t, the height of the classification marks could likewise be 50 mm and at least 25 mm for the expiry dates.

The classification and expiry marks shall at least be affixed externally on both sides in the upper corners near the front.

The marks shall be as follows:

| <u>Equipment</u>   | <u>Distinguishing mark</u> |
|--|----------------------------|
| Normally insulated equipment                                       | IN                         |
| Heavily insulated equipment  | IR                         |
| Class A refrigerated equipment with normal insulation              | RNA                        |
| Class A refrigerated equipment with heavy insulation               | RRA                        |
| Class B refrigerated equipment with heavy insulation               | RRB                        |
| Class C refrigerated equipment with heavy insulation               | RRC                        |
| Class D refrigerated equipment with normal insulation              | RND                        |
| Class D refrigerated equipment with heavy insulation               | RRD                        |
| Class A mechanically refrigerated equipment with normal insulation | FNA                        |
| Class A mechanically refrigerated equipment with heavy insulation  | FRA                        |
| Class B mechanically refrigerated equipment with heavy insulation  | FRB                        |
| Class C mechanically refrigerated equipment with heavy insulation  | FRC                        |
| Class D mechanically refrigerated equipment with normal insulation | FND                        |
| Class D mechanically refrigerated equipment with heavy insulation  | FRD                        |



| <u>Equipment</u>  | <u>Distinguishing<br/>mark</u> |
|---|--------------------------------|
| Class E mechanically refrigerated equipment with heavy insulation | FRE                            |
| Class F mechanically refrigerated equipment with heavy insulation | FRF                            |
| Class A heated equipment with normal insulation                   | CNA                            |
| Class A heated equipment with heavy insulation                    | CRA                            |
| Class B heated equipment with heavy insulation                    | CRB                            |
| Class C heated equipment with heavy insulation                    | CRC                            |
| Class D heated equipment with heavy insulation                    | CRD                            |

If the equipment is fitted with a removable or non-independent thermal appliance and if special conditions exist for the use of the thermal appliance, the distinguishing mark or marks shall be supplemented by the letter X in the following cases:

1. FOR REFRIGERATED EQUIPMENT:

Where the eutectic plates have to be placed in another chamber for freezing;

2. FOR MECHANICALLY REFRIGERATED EQUIPMENT:

2.1 Where the compressor is powered by the vehicle engine;

2.2 Where the refrigeration unit itself or a part is removable, which would prevent its functioning.

The date (month, year) entered under section A, item 8 in appendix 3 of this annex as the date of expiry of the certificate issued in respect of the equipment shall be quoted under the distinguishing mark or marks aforesaid.

Model:

|                          |
|--------------------------|
| <p>FRC<br/>02 - 2020</p> |
|--------------------------|

02 = month (February) ) of expiry of the  
2020= year ) certificate

## Annex 2

### **SELECTION OF EQUIPMENT AND TEMPERATURE CONDITIONS TO BE OBSERVED FOR THE CARRIAGE OF QUICK (DEEP)-FROZEN AND FROZEN FOODSTUFFS**

1. For the carriage of the following quick (deep)-frozen and frozen foodstuffs, the transport equipment has to be selected and used in such a way that during carriage the highest temperature of the foodstuffs at any point of the load does not exceed the indicated temperature.

By that means the equipment used for the transport of quick-frozen foodstuffs shall be fitted with the device referred to in appendix 1 to this annex. If however one should proceed to the verification of the temperature of the foodstuff, this shall be done according to the procedure laid down in appendix 2 to this annex.

2. Accordingly, the temperature of the foodstuffs at any point in the load must be at or below the indicated value on loading, during carriage and on unloading.
3. Where it is necessary to open the equipment, e.g. to carry out inspections, it is essential to ensure that the foodstuffs are not exposed to procedures or conditions contrary to the objectives of this annex and those of the International Convention on the Harmonization of Frontier Controls of Goods.
4. During certain operations, such as defrosting the evaporator of mechanically refrigerated equipment, a brief rise of the temperature of the surface of the foodstuffs of not more than 3 °C in a part of the load, e.g. near the evaporator, above the appropriate temperature may be permitted.

|  |        |
|--|--------|
| Ice cream .....  | -20 °C |
| Frozen or quick (deep)-frozen fish, fish products,<br>molluscs and crustaceans and all other<br>quick (deep)-frozen foodstuffs ..... | -18 °C |
| All other frozen foodstuffs (except butter) .....  | -12 °C |
| Butter .....   | -10 °C |

Deep-frozen and frozen foodstuffs mentioned below to be immediately further processed at destination: <sup>1</sup>

Butter  
Concentrated fruit juice

---

<sup>1</sup> *The deep-frozen and frozen foodstuffs listed, when intended for immediate further processing at destination, may be permitted gradually to rise in temperature during carriage so as to arrive at their destination at temperatures no higher than those specified by the sender and indicated in the transport contract. This temperature should not be higher than the maximum temperature authorized for the same foodstuff when refrigerated as mentioned in annex 3. The transport document shall state the name of the foodstuff, whether it is deep-frozen or frozen and that it is immediately to be further processed at destination. This carriage shall be undertaken with ATP-approved equipment without use of a thermal appliance to increase the temperature of the foodstuffs.*



## **Annex 2, Appendix 1**

### **MONITORING OF AIR TEMPERATURES FOR TRANSPORT OF PERISHABLE FOODSTUFFS QUICK-FROZEN**

The transport equipment shall be fitted with an instrument capable of measuring and recording air temperatures and storing the data obtained (hereinafter referred to as the instrument) to monitor the air temperatures to which quick-frozen foodstuffs intended for human consumption are subjected.

The instrument shall be verified in accordance with EN 13486 (Temperature recorders and thermometers for the transport, storage and distribution of chilled, frozen, deep-frozen/quick-frozen food and ice cream – Periodic verification) by an accredited body and the documentation shall be available for the approval of ATP competent authorities.

The instrument shall comply with standard EN 12830 (Temperature recorders for the transport, storage and distribution of chilled, frozen, deep-frozen/quick-frozen food and ice cream – Tests, performance, suitability).

Temperature recordings obtained in this manner must be dated and stored by the operator for at least one year or longer, according to the nature of the food.



## Annex 2, Appendix 2

### **PROCEDURE FOR THE SAMPLING AND MEASUREMENT OF TEMPERATURE FOR CARRIAGE OF CHILLED, FROZEN AND QUICK-FROZEN PERISHABLE FOODSTUFFS**

#### **A. GENERAL CONSIDERATIONS**

1. Inspection and measurement of temperatures stipulated in annexes 2 and 3 should be carried out so that the foodstuffs are not exposed to conditions detrimental to the safety or quality of the foodstuffs. Measuring of food temperatures should be carried out in a refrigerated environment, and with the minimum delays and minimum disruption of transport operations.
2. Inspection and measurement procedures, as referred to in paragraph 1, shall preferably be carried out at the point of loading or unloading. These procedures should not normally be carried out during transport, unless serious doubt exists about the conformity of the temperatures of the foodstuffs stipulated in annexes 2 and 3.
3. Where possible, the inspection should take account of information provided by temperature monitoring devices during the journey before selecting those loads of perishable foodstuffs for sampling and measurement procedures. Progression to temperature measurement of the food should only be undertaken where there is reasonable doubt of the temperature control during carriage.
4. Where loads have been selected, a non-destructive measurement (between-case or between-pack) should at first be used. Only where the results of the non-destructive measurement do not conform with the temperatures laid down in annexes 2 or 3 (taking into account allowable tolerances), are destructive measurements to be carried out. Where consignments or cases have been opened for inspection, but no further action has been taken, they should be resealed giving the time, date, place of inspection, and the official stamp of the inspection authority.

#### **B. SAMPLING**

5. The types of package selected for temperature measurement shall be such that their temperature is representative of the warmest point of the consignment.
6. Where it is necessary to select samples during transport whilst the consignment is loaded, two samples should be taken from the top and bottom of the consignment adjacent to the opening edge of each door or pair of doors.
7. Where samples are taken during unloading of the consignment, four samples should be chosen from any of the following locations:
  - top and bottom of the consignment adjacent to the opening edge of the doors;
  - top rear corners of the consignment (i.e. furthest away from the refrigeration unit);
  - centre of the consignment;
  - centre of the front surface of the consignment (i.e. closest to the refrigeration unit);
  - top or bottom corners of the front surface of the consignment (i.e. closest to the return air intake of the refrigeration unit).

8. In the case of chilled foods in annex 3, samples should also be taken from the coldest location to ensure that freezing has not occurred during transportation.

### **C. TEMPERATURE MEASUREMENT OF PERISHABLE FOODSTUFFS**

9. The temperature measuring probe should be precooled to as close to the product temperature as possible before measurement.

#### ***I. Chilled foods***

10. Non-destructive measurement. Measurement between-case or between-pack should be made with a probe with a flat head, which gives a good surface contact, low thermal mass, and high thermal conductivity. When placing the probe between the cases or food packs, there should be sufficient pressure to give a good thermal contact, and sufficient length of probe inserted to minimize conductivity errors.

11. Destructive measurement. A probe with a rigid, robust stem and sharpened point should be used, made from a material which is easy to clean and disinfect. The probe should be inserted into the centre of the food pack, and the temperature noted when a steady reading is reached.

#### ***II. Frozen and quick-frozen foods***

12. Non-destructive measurement. Same as paragraph 10.

13. Destructive measurement. Temperature probes are not designed to penetrate frozen foods. Therefore it is necessary to make a hole in the product in which to insert the probe. The hole is made by a precooled product penetration instrument, which is a sharp pointed metallic instrument such as an ice punch, hand drill or an auger. The diameter of the hole should provide a close fit to that of the probe. The depth to which the probe is inserted will depend on the type of product:

- (i) Where product dimensions allow, insert the probe to a depth of 2.5 cm from the surface of the product;
- (ii) Where (i) is not possible because of the size of the product, the probe should be inserted to a minimum depth from the surface of 3 to 4 times the diameter of the probe;
- (iii) It is not possible or practical to make a hole in certain foods because of their size or composition e.g. diced vegetables. In these cases, the internal temperature of the food package should be determined by insertion of a suitable sharp-stemmed probe to the centre of the pack to measure the temperature in contact with the food.

After inserting the probe, the temperature should be read when it has reached a steady value.

### **D. GENERAL SPECIFICATIONS FOR THE MEASURING SYSTEM**

14. The measuring system (probe and read-out) used in determining temperature shall meet the following specifications:

- (i) the response time should achieve 90% of the difference between the initial and final reading within three minutes;

- (ii) <sup>1</sup> the system must have an accuracy of  $\pm 0.5$  °C within the measurement range -20°C to + 30 °C;
- (iii) <sup>1</sup> the measuring accuracy must not change by more than 0.3 °C during operation in the ambient temperature range -20°C to + 30°C;
- (iv) the display resolution of the instrument should be 0.1 °C;
- (v) <sup>1</sup> the accuracy of the system should be checked at regular intervals;
- (vi) the system should have a current certificate of calibration from an approved institution;
- (vii) the electrical components of the system should be protected against undesirable effects due to condensation of moisture;
- (viii) the system should be robust and shock proof.

## **E. ALLOWABLE TOLERANCES IN THE MEASUREMENT OF TEMPERATURE**

15. Certain tolerances should be allowed in the interpretation of temperature measurements:

- (i) operational - in the case of frozen and quick-frozen foods, a brief rise of up to 3 °C on the temperature permitted in annex 2 is allowed for the surface temperature of the food;
- (ii) methodology - non-destructive measurement can give up to a maximum of 2°C difference in the reading compared to the true product temperature measurement, especially with the thickness of cardboard in case packaging. This tolerance does not apply to the destructive measurement of temperature.

---

<sup>1</sup> *The procedure will be defined.*





### Annex 3

#### **SELECTION OF EQUIPMENT AND TEMPERATURE CONDITIONS TO BE OBSERVED FOR THE CARRIAGE OF CHILLED FOODSTUFFS**

1. For the carriage of the following chilled foodstuffs, the transport equipment has to be selected and used in such a way that during carriage the highest temperature of the foodstuffs at any point of the load does not exceed the indicated temperature. If, however, the verification of the temperature of the foodstuff is carried out, it shall be done according to the procedure laid down in Appendix 2 to Annex 2 to this Agreement.
2. Accordingly, the temperature of the foodstuffs at any point in the load must not exceed the temperature as indicated below on loading, during carriage and on unloading.
3. Where it is necessary to open the equipment, e.g. to carry out inspections, it is essential to ensure that the foodstuffs are not exposed to procedures or conditions contrary to the objectives of this Annex and those of the International Convention on the Harmonization of Frontier Controls of Goods.
4. The temperature control of foodstuffs specified in this Annex should be such as not to cause freezing at any point of the load.

|      |  | <i>Maximum temperature</i>  |
|------|--|---|
| I.   | Raw milk <sup>1</sup>  | + 6 °C  |
| II.  | Red meat <sup>2</sup> and large game (other than red offal)  | + 7 °C  |
| III. | Meat products, <sup>3</sup> pasteurized milk, butter, fresh dairy products (yoghurt, kefir, cream and fresh cheese <sup>4</sup> ), ready cooked foodstuffs (meat, fish, vegetables), ready to eat prepared raw vegetables and vegetable products <sup>5</sup> , concentrated fruit juice and fish products <sup>3</sup> not listed below | Either at + 6 °C or at temperature indicated on the label and/or on the transport documents |
| IV.  | Game (other than large game), poultry <sup>2</sup> and rabbits   | + 4 °C  |
| V.   | Red offal <sup>2</sup>   | + 3 °C  |
| VI.  | Minced meat <sup>2</sup>   | Either at +2 °C or at temperature indicated on the label and/or on the transport documents  |
| VII  | Untreated fish, molluscs and crustaceans <sup>6</sup>  | On melting ice or at temperature of melting ice   |

<sup>1</sup> When milk is collected from the farm for immediate processing, the temperature may rise during carriage to +10 °C.

<sup>2</sup> Any preparations thereof.

<sup>3</sup> Except for products fully treated by salting, smoking, drying or sterilization.

<sup>4</sup> "Fresh cheese" means a non-ripened (non-matured) cheese which is ready for consumption shortly after manufacturing and which has a limited conservation period.

<sup>5</sup> Raw vegetables which have been diced, sliced or otherwise size reduced, but excluding those which have only been washed, peeled or simply cut in half.

<sup>6</sup> Except for live fish, live molluscs and live crustaceans.

# ATP

as amended on 30 September 2015

The Agreement on the International Carriage of Perishable Foodstuffs and on the Special Equipment to be Used for such Carriage (ATP) done at Geneva on 1 September 1970 entered into force on 21 November 1976.

The Agreement and its annexes have been regularly amended and updated since their entry into force by the Working Party on the Transport of Perishable Foodstuffs (WP.11) of the United Nations Economic Commission for Europe's Inland Transport Committee.

At the time of publishing, the Contracting Parties to ATP are Albania, Andorra, Austria, Azerbaijan, Belarus, Belgium, Bosnia and Herzegovina, Bulgaria, Croatia, Czech Republic, Denmark, Estonia, Finland, France, Georgia, Germany, Greece, Hungary, Ireland, Italy, Kazakhstan, Kyrgyzstan, Latvia, Lithuania, Luxembourg, Monaco, Montenegro, Morocco, Netherlands, Norway, Poland, Portugal, Republic of Moldova, Romania, Russian Federation, Saudi Arabia, Serbia, Slovakia, Slovenia, Spain, Sweden, Tajikistan, The former Yugoslav Republic of Macedonia, Tunisia, Turkey, Ukraine, United Kingdom of Great Britain and Northern Ireland, United States of America, Uzbekistan.

Information Service  
United Nations Economic Commission for Europe

Palais des Nations  
CH - 1211 Geneva 10, Switzerland  
Telephone: +41(0)22 917 44 44  
Fax: +41(0)22 917 05 05  
E-mail: [info.ece@unece.org](mailto:info.ece@unece.org)  
Website: <http://www.unece.org>

Printed at United Nations, Geneva  
1509797 (E)–June 2015–632  
**ECE/TRANS/249**

United Nations publication  
Sales No E.15.VIII.2

ISBN 978-92-1-139153-4



9 789211 391534