

Draft proposal to introduce “side illuminating lamp” to Regulation No. 119 and Regulation No. 48

There are presented additional descriptions which are analogical to cornering lamp. They have additional letter A to easy comparisons to cornering lamps.


In Regulation No 119

- 1.1.A "Side illuminating lamp" means a lamp used to provide supplementary illumination of that part of the road which is located on the left side of vehicle to improve road visibility for oncoming drivers in situation when they are exposed for headlights glare.
- 6.2.A The minimum intensity of the light between the specified measuring points shall be not less than 500 cd and below the 2.5 D and above 30D, 80 FRONT and 80 REAR line and at the specified measuring points shall be as follows:
- (1) 2.5D – 60 FRONT : 1000 cd
 - (2) 2.5D – 0 SIDE: 500 cd
 - (3) 2.5D – 60REAR: 1000 cd
- 6.3.A The intensity of the light emitted in all directions shall not exceed:
- (a) 1 cd above the 1.0U, 90 FRONT and 90 REAR line;
 - (b) 100 cd between the horizontal plane and the 1.0U, L and R Line; and
 - (c) 14,000 cd below the 2.5 D, 80 FRONT and 80 REAR line;
 - (d) 100 cd below the 0.57 D, in directions not prescribed above.

In Annex 3

- 2.A Measuring points expressed in degrees of angle with the axis of reference


Figure 1A



○ = Minimum intensity in cd

2.1. Field of geometric visibility

Figure 1



In Regulation 48

2.7.26.A "Side illuminating lamp" means a lamp used to provide supplementary illumination of that part of the road which is located on the left side of vehicle to improve road visibility for oncoming drivers in situation when they are exposed for headlights glare.

6.20.A **Side illuminating** lamp (Regulation No. 119)

6.20.1.A Presence
Optional on motor vehicles.

6.20.2.A Number

