



Informal document No. 22
(85th GRSG, 21-24 October 2003
agenda item 1)

OICA PROPOSAL FOR DRAFT AMENDMENTS TO DOCUMENT
TRANS/WP.29/GRSG/2003/18
UN/ECE R36 (BUS CONSTRUCTION)

A. Proposal

Draft new para. 5.7.8.5.1 of Part 5, amend to read:

"5.7.8.5.1. For a seat behind a partition or other rigid structure other than a seat, a minimum clear space in front of each passenger seat shall be provided as shown in Annex 3, figure 8a. **Alternatively A** partition whose contour corresponds approximately to that of the inclined seat back may intrude into this space as provided by paragraph 5.7.8.4. "

New inserted para. 5.7.8.5.2, amend to read:


"5.7.8.5.2. For a seat behind a seat and/or a seat facing the gangway, a minimum clear foot space of at least 300 mm depth and a width according to paragraph 5.7.8.1.1., **reduced where appropriate by paragraph 5.7.8.6.**, shall be provided **as shown in Annex 3, figure 8b**. The local presence in this space of seat legs shall be permitted provided that adequate space remains for the passengers' feet. This foot space may partly be situated in and/or above the gangway but shall not create any obstruction when measuring the gangway-width in accordance with paragraph 5.7.5. "

Annex 3, figure 8, amend to read:

"Figure 8a
Space for seated passengers behind a partition
or other rigid structure other than a seat
(see paragraph 5.7.8.5.1)"

Insert a new drawing:

Figure 8b
"Space for seated passengers behind a seat
and or/ or a seat facing the gangway
(see paragraph 5.7.8.5.2)"



B. Justification:

The intention of the proposal is:

1. to clarify the interpretation of paragraph 5.7.8.5.1. and Annex 3 figure 8, which was intended not to impose any additional requirements on seat spacing but instead to determine the clear space between a passenger seat and a partition or other rigid structure other than a seat, and
2. to clarify that the foot space in front of each passenger seat may be so located that parts of the foot space "intrude" into the gangway, either on the floor or above it. In any case, while measuring the gangway width with the respective testing gauge, the foot space shall not obstruct movement of the gauge.